

**SURVEY & REMONUMENTATION**

APR 25 1995

RC 1423

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA280

For corners in

Wayne (County) Located In: Corner Code #

Dearborn Township #09

|                                    |            |     |
|------------------------------------|------------|-----|
| 1. Public Land Survey              | T 2S R 10E | L-5 |
|                                    | T R        |     |
|                                    | T R        |     |
|                                    | T R        |     |
| 2. Property Controlling in Section | S T R      |     |
|                                    | S T R      |     |
| 3. Miscellaneous Property in Sec.  | S T R      |     |
|                                    | S T R      |     |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/6/94 [Signature]

WAYNE COUNTY REMONUMENTATION FEE GROUP COMMITTEE

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Lawrence R. Feindt, in a field survey on September 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-5) 1/4 Corner Common to Sections 12 and 13, T 2 S, R 10 E

|                                    |   |
|------------------------------------|---|
| GENERAL LAND OFFICE                | 3" BRASS CAP INSIDE MONUMENT BOX                |
| SET POST FOR CORNER                | N45-E- 67.44'-SPIKE IN NW SIDE TEL. POLE        |
| LYNWOOD 10"-N30 W 33 LINKS(21.78') | S45-W- 33.52'-MSHD TAG IN NW SIDE OF 19" OAK    |
| BEECH 12"-S45 W-36 LINKS(23.76')   | N55 W- 60.77'-MSHD TAG IN SW SIDE OF 20" LOCUST |
| DECEMBER 19, 1816                  | MARCH 8, 1964                                   |
| BY: JOSEPH FLETCHER, DS            | BY: BERNARD J. SWIEBODA, SURVEY CHIEF - MDOT    |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5) 1/4 Corner Common to Sections 12 and 13, T 2 S, R 10 E  
Found 3" brass disk in monument box as documented by the Michigan Department of Transportation in 1964. Distance to M-5 measured 2683.78' (MDOT = 2683.90'). Corner was confirmed with irons found in "Fairlane office Park" as recorded in Liber 93 of Plats, Page 55; and "Shops at Fairlane Meadows" as recorded in Liber 104, Page 91.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5) 1/4 Corner Common to Sections 12 and 13, T 2 S, R 10 E  
Found 3" brass disk in monument box on the Northerly edge of East bound Ford Road. Road surface is concrete. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N31°W - 7.71' - Set PK nail in concrete curb and affixed Wayne County brass disk stamped with license #21566

N01°E - 44.00' - Found "X" cut in concrete curb

S29°W - 73.33' - Found OHM-KSW cap #21584 in SE face of power pole

S29°E - 72.19' - Set "X" cut in top center of fire hydrant

S66°E - 165.58' - Set nail and #21566 cap in SW face of power pole

Signed by Lawrence R. Feindt Date 12/21/94

Surveyor's Michigan License No. 21566

2 R  
11D-MISC