

**SURVEY & REMONUMENTATION**

APR 25 1995

COMMISSION

RC 1424

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA281

For corners in

<u>Wayne</u> <small>(County)</small>	Located In:	Corner Code <u>11</u>
<u>Dearborn Township #09</u>		
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12/6/94 DPJ  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Lawrence R. Feindt, in a field survey on September 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-2) East 1/4 Corner of Section 1, T 2 S, R 10 E  
GENERAL LAND OFFICE  
SET POST FOR CORNER  
BEECH 16"-881 W-26 LINKS(17.16')  
BEECH 16"-N64 E-31 LINKS(20.46')  
DECEMBER 16, 1816  
BY: JOSEPH FLETCHER, DS

\$ 13.00 MISCELLANEOUS RECORDING  
21 DEC 94 8:25 A.M. RECEIPT# 1A  
RECEIVED  
OFFICE OF THE REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2) East 1/4 Corner of Section 1, T 2 S, R 10 E  
Found 1/2" pipe in monument box. Distance to M-3 measured 2634.47' (WCRC plans for Greenfield Road dated March 1947 = 2634.11'). Corner was confirmed with irons found in "Warren Grove Subdivision" as recorded in Liber 40 of Plats, Page 91; and "Gaynor Park Subdivision No. 1" as recorded in Liber 46 of Plats, Page 64.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2) East 1/4 Corner of Sections 1, T 2 S, R 10 E  
Found 1/2" pipe in monument box at the intersection of Tireman Avenue and Greenfield Avenue. Road surface is asphalt. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.  
Witnesses: N35°E - 43.00' - Set PK nail in SW face of power pole and affixed Wayne County brass disk stamped with license #21566  
S47°W - 58.31' - Found RLS cap #4018 in SE face of power pole  
N42°W - 65.45' - Found RLS cap #4018 in NE face of power pole  
S55°E - 43.76' - Set "X" cut in West bolt of traffic light pole

Signed by Lawrence R. Feindt Date 12/21/94  
Surveyor's Michigan License No. 21566

ZR  
11 D-misc