

**SURVEY &  
REMONUMENTATION**

APR 25 1995

RC 1425

LI27792PA282

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Wayne</u> (County)	Located In:	Corner Code #
<u>Dearborn Township #09</u>		
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12/6/94 DRJ  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Lawrence R. Feindt, in a field survey on September 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-3) East Corner Common to Sections 1 and 12, T 2 S, R 10 E

GENERAL LAND OFFICE  
SET POST FOR CORNER  
BEECH 16"-N25°E-14 LINKS(9.24')  
BEECH 12"-N46°W-30 LINKS(19.80')  
DECEMBER 16, 1816  
BY: JOSEPH FLETCHER, DS

\* 15.00 MICHIGAN DEEDS RECORDING  
21 DEC 94 10:30 AM  
REGISTERED LAND SURVEYORS

CORNER IS RECITED BY GLO NOTES AS BEING COMMON TO THE WEST CORNER OF SECTIONS 6 AND 7, T 2 S, R 11 E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3) East Corner Common to Section 1 and 12, T 2 S, R 10 E

Found brass disk in monument box. Distance to M-2 measured 2634.47' (WCRC plans for Greenfield Road dated March 1947 = 2634.11') and distance to M-4 measured 2635.72' (WCRC plans = 2635.70'). Corner was confirmed with irons found in "Melrose Gardens Subdivision" as recorded in Liber 42 of Plats, Page 95; "West Warren Ave. Estates" as recorded in Liber 43 of Plats, Page 65; "West Warren Ave. Estates No. 1" as recorded in Liber 43 of Plats, Page 70; and "Warren Vineyards Subdivision" as recorded in Liber 45, Page 59.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3) East Corner Common to Sections 1 and 12, T 2 S, R 10 E

Found brass disk in monument box 15"± deep at the intersection of Warren Avenue and Greenfield Road. Road surface is asphalt. Raised to surface with "T"-iron and placed Wayne County brass disk stamped with license #21566 atop T-iron. Corner is accepted as a careful and faithful **reestablishment** of the position of the original corner.

Witnesses: N43°W - 80.50' - Set nail and #21566 cap in SW face of power pole  
N23°E - 70.46' - Found nail in NW face of power pole  
S22°E - 67.09' - Found nail in NE face of power pole  
S41°W - 96.98' - Set "X" cut in North bolt on base of guy anchor pole

Signed by Lawrence R. Feindt Date 12/21/94  
Surveyor's Michigan License No. 21566

2R  
11-0-MISC