

SURVEY & REMONUMENTATION

APR 25 1995

RC 1426

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA283

For corners in

Wayne (County) Located In: Corner Code #1
Dearborn Township #09

1. Public Land Survey	T 2S R 10E	M-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12/6/94 D.J.
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Lawrence R. Feindt, in a field survey on September 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-4) East 1/4 Corner of Section 12, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER ELM 9"-N55°E-12 LINKS(7.92') ELM 10"-N16°E-22 LINKS(14.52') DECEMBER 16, 1816 BY: JOSEPH FLETCHER, DS	M.D.O.T. 3/4" PIPE IN MONUMENT BOX N35°W- 24.17'-CHISELED "X" ON RIM OF SEWER MH N50°E- 51.65'-SW CORNER BUILDING #6400 S55°E- 53.92'-NW CORNER BUILDING #6356 DATE: MARCH 2, 1964 BY: BERNARD J. SWIEBODA, SURVEY CHIEF
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4) East 1/4 Corner of Section 12, T 2 S, R 10 E

Found 1/2" pipe in monument box. Distance to M-3 measured 2635.72' (WCRC plans for Greenfield Road dated March 1947 = 2635.70') and distance to M-5 measured 2635.33' (MDOT = 2635.11'). Corner was confirmed with irons found in "Laurel Park subdivision" as recorded in Liber 46 of Plats, Page 69.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4) East 1/4 Corner of Sections 12, T 2 S, R 10 E

Found 1/2" pipe in monument box at the intersection of Paul Avenue and Greenfield Road. Road surface is asphalt. Placed Wayne County brass disk stamped with license #21566 over pipe. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: S64°W - 90.12' - Set nail and #21566 cap in East face of power pole
N42°W - 41.93' - Set nail and #21566 cap in NE face of power pole
N49°E - 51.50' - SW corner of building #6400 (MDOT witness)
S53°E - 53.65' - NW corner of building #6356 (MDOT witness)

Signed by Lawrence R. Feindt Date 12/21/94
Surveyor's Michigan License No. 21566

2 R
11 D - Misc