

SURVEY & REMONUMENTATION

APR 25 1995

RC 1427

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA284

For corners in

Wayne (County) Located In: Corner Code #/

Dearborn Township #09

1. Public Land Survey T 2S R 10E M-5

2. Property Controlling in Section S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/1/94 [Signature]

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Lawrence R. Feindt, in a field survey on September 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5) East Corner Common to Sections 12 and 13, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER ELM 12"-N55°E-5 LINKS(3.30')	M.D.O.T. BRASS CAP IN MONUMENT BOX ON BRIDGE CAP N25°E- 84.80'-DRILL HOLE IN SQUARE SE CORNER LIGHT POLE S40°E- 62.21'-CHISELED "X" ON RIM OF MANHOLE S12°E- 52.28'-DRILL HOLE IN SQUARE NE CORNER LIGHT POLE DATE: MARCH 2, 1964
BEECH 10"-N47°W-24 LINKS(15.84') DECEMBER 16, 1818 BY: JOSEPH FLETCHER, DS	BY: BERNARD J. SWIEBODA, SURVEY CHIEF

CORNER IS RECITED BY GLO NOTES AS BEING COMMON TO THE WEST CORNER OF SECTIONS 7 AND 18, T 2, R 11 E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5) East Corner Common to Sections 12 and 13, T 2 S, R 10 E

Found brass cap in monument box. Distance to M-4 measured 2635.33' (MDOT= 2635.11'), distance to M-6 measured 2636.25' (MDOT = 2636.18') and distance to L-5 measured 2683.78' (MDOT = 2683.90'). Corner was confirmed with irons found in "Shops at Fairlane Meadows" as recorded in Liber 104 of Plats, Page 91.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5) East Corner Common to Sections 12 and 13, T 2 S, R 10 E

FOUND BRASS CAP IN MONUMENT BOX AS DOCUMENTED BY THE MICHIGAN DEPARTMENT OF TRANSPORTATION IN THE NORTH BOUND LAINE OF THE GREENFIELD ROAD BRIDGE DECK OVER FORD ROAD. ROAD SURFACE IS CONCRETE. CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Witnesses: S89°E - 20.40' - Set PK nail in concrete curb and affixed Wayne County brass disk stamped with license #21566.

N15°E - 84.73' - Found "X" cut in SW bolt of light pole
 N16°E - 84.92' - Found drill hole in SE corner base of light pole (MDOT witness)
 S25°E - 51.81' - Found "X" cut in NW bolt of light pole
 S49°E - 62.18' - Found "X" cut in rim of manhole (MDOT witness)
 N42°W - 110.44' - Found "X" cut in SE bolt of light pole
 S58°W - 88.25' - Found "X" cut in NE bolt of light pole

Signed by Lawrence R. Feindt Date 12/21/94

Surveyor's Michigan License No. 21566