

**SURVEY &
REMONUMENTATION**

RC 1428

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA285

For corners in

Wayne
(County)
Dearborn Township #09

Located In:

Corner Code: M-6

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>2S</u> | R | <u>10E</u> | <u>M-6</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12/16/94 *DBJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**Lawrence R.
Feindt**

I, Feindt, in a field survey on September 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6) East 1/4 Corner of Section 13, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER W. WALNUT 10"-N88°W-19 LINKS(12.54') WHITE ASH 10"-S41°W-18 LINKS(11.88') DECEMBER 16, 1816 BY: JOSEPH FLETCHER, DS	M.D.O.T. CONCRETE MONUMENT IN MONUMENT BOX S25°W- 34.35'-N & C IN 16" ELM N55°E- 46.68'-NW CORNER BUILDING #4898 EAST - 26.80'-N & C LIGHT POLE DATE: MARCH 2, 1964 BY: BERNARD J. SWIEBODA, SURVEY CHIEF
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6) East 1/4 Corner of Section 13, T 2 S, R 10 E

Found concrete monument in monument box. Distance to M-5 measured 2636.25' (MDOT= 2636.18'). Corner was confirmed from irons and ties depicted on "Shops at Fairlane Meadows" as recorded in Liber 104 of Plats, Page 91.

[Faint stamps and handwritten notes]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5) East 1/4 Corner of Section 13, T 2 S, R 10 E

Found concrete monument in monument box as documented by the Michigan Department of Transportation and placed Wayne County brass disk stamped with license #21566 over iron rod in monument. Corner is in the North bound lane of Greenfield Road Southerly of Hubbard Drive. Road surface is asphalt. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N86°E - 26.64' - Found MDOT nail & cap in South face of power pole (MDOT witness)
N59°E - 46.52' - NW corner of building #4898 (MDOT witness)
N22°E - 103.78' - Found PK nail in SE face of power pole
N30°W - 117.03' - Found PK nail in East face of power pole

Signed by Lawrence R. Feindt Date 12/21/94

Surveyor's Michigan License No. 21566

Z R
11 D-MISC.