

FEB 28 2000

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 19--

SECTION

For corners in

Wayne (County) Located In: Springwells Twp. City of Dearborn Corner Code # B-3
1. Public Land Survey T-2-S R-11-E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Liber-30803 Page-1
99585580 12/20/1999
F.E. Youngblood, Wayne Co. Register of Deeds

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, John N. Redash, in a field survey on Dec. 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1816) South 1/4 corner Section 6, North 1/4 corner Section 7 (Description of corner not stated)

City of Dearborn Engineering Brass Plug F.B. 1048, Page 55.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A brass disk in existing monument box currently occupies this corner. Field measurements were observed between the following corners:

- A-3 to B-3 2610.61 meas. 2634.72 Rec. G.L.O. 2610.05 Rec. sum of plats "Warren Vineyards Sub" "Warren Grove Sub" Liber 45, Page 59 Liber 40, Page 91
B-2 to B-3 2657.11 Meas 2655.77 Rec. Plat 2657.0 Rec. Plat "Warren Grove Sub" "Columbia Park No. 1" Liber 40, Page 91 Liber 38, Page 46
B-3 to C-3 2622.46 Meas. 2622.20 Rec. sum of plats 2634.72 Rec. G.L.O. "Columbia Park Sub" "Columbia Park Sub No. 1" Liber 36, Page 47 Liber 38, Page 46
B-3 to B-4 2626.95 Meas. No G.L.O. 2628.00 Rec sum of plats "Warren & Chase Sub" "A.P. Ternes Sub No. 1" "A.P. Ternes Sub No. 2" "A.P. Ternes Sub 1" Liber 42, Page 96 Liber 40, Page 72 Liber 40, Page 91 Liber 40, Page 12

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3, South 1/4 corner of Section 6 and the north 1/4 corner of Section 7, T-3-S., R-11-E.

Raised existing brass disk with a 1/2" iron rod in concrete with a remonumentation aluminum disk stamped #37281 at the intersection of Warren and Chase Roads and it is accepted as a careful and faithful perpetuation of the position of the original corner.

- Witnesses: N 26° E., 83.09 feet Found P.K. nail with Wayne County Road Comm. tag E. face U-pole
S 33° E., 52.51 feet Found cut cross in S.W. bolt light pole
S 30° W., 66.25 feet Found P.K. nail with Wayne County Road Comm. tag S.E. face U-pole
N 16° W., 56.54 feet Found 40d nail with Wayne County Road Comm. tag E. face U-pole

Signed by [Signature]

Date 12-15-99

Surveyor's Michigan License No. 37281

Grid table with columns A-L and rows 1-13. Cell (3, B) contains a circled '2'.

\$4.00 REMONUMENTATION
Receipt #19151

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

\$9.00 DEED



R LCR 9 4R 1Pg A [Signature]