

LAND CORNER RECORDATION CERTIFICATE LIBER 28452 PAGE 755
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In: **GREENFIELD TWP**
(NOW CITY OF DETROIT) *Common Cor.*

Corner Code #

1. Public Land Survey

T ~~18~~ R ~~11E~~

C-13

T 25 R 11E

C-01 ✓

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: **DEC 5 1995** *ncd.*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, STEVEN E. DUNN, in a field survey on OCTOBER 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED 3, SEPT. 1916

PLATS

L. 31 P. 13
 L. 54 P. 90
 L. 48 P. 58

**ROBERT M GRINDLEY'S SUBDIVISION NO. 6 OF LITTLE FARMS
 GREENFIELD IMPROVEMENT SALES CO.'s GREENFIELD-MONNIER RE-SUB
 ROBERT OAKMAN LAND COMPANY'S AVIATION FIELD SUB. NO. 4.**

**AUGUST 6, 1914
 MAY 28, 1925
 DECEMBER 22, 1925**

95263070

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 T.1S, R.11E. COMMON TO E-1 T.2S, R.11E.

NO EVIDENCE OF CORNER FOUND

RE-ESTABLISHED NORTH LINE OF JOY ROAD USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMAN'S LAND COMPANY SUB" L. 52 P. 86. RE-ESTABLISHED EAST LINE OF WYOMING USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMAN'S LAND COMPANY SUB" L. 43 P. 95. VERIFIED LOCATION WITH STONE CURB SPLITS AND SIDEWALK SPLITS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

C-13 TO B-13 2635.43' (M.)
 C-13 TO C-12 2640.36' (M.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON ROD WITHIN A MONUMENT BOX.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 T.1S., R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

AZ. 318° 97.01' SET PK NAIL AND W.C.R. TAG IN SOUTHEAST CORNER OF BUILDING #8801
 AZ. 213° 50.11' SET PK NAIL AND W.C.R. TAG IN WEST FACE OF UTILITY POLE
 AZ. 295° 68.34' SET PK NAIL AND W.C.R. TAG IN SOUTHWEST FACE OF UTILITY POLE
 AZ. 67° 63.03' SET PK NAIL AND W.C.R. TAG IN NORTHWEST FACE OF UTILITY POLE

*4
7 D
710.*

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Steven E. Dunn Date DECEMBER 5, 1995
 Surveyor's Michigan License No. 28408