

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 28 2000

SECTION

For corners in

Wayne (County) Located In: Springwells Twp. City of Dearborn Corner Code #
1. Public Land Survey T-2-S R-11-E D-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Liber-30803 Page-2
99585582 12/20/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, John N. Redash, in a field survey on December 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1816) South 1/4 corner of Section 5, North 1/4 corner of Section 8 (Description of corner not stated)

Witnesses as:

10" Sugar maple N. 22° W., 16 links (gone)
6" D.O. S. 01° W., 6 links (gone)

City of Dearborn Engineering brass plug F.B. 1048, Page 59.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A brass disk in an existing monument box is currently occupying this corner's position. Field measurements were obtained between the following corners:

Table with 3 columns: Corner pair, Measurement, and Reference. Includes entries for D-3 to E-3, C-3 to D-3, and D-3 to D-4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3, South 1/4 corner of Section 5 and the North 1/4 corner of Section 8, T-2-S., R-11-E. Raised existing brass disk with a 1/2" iron rod in concrete with a remonumentation aluminum disk stamped #37281 at the intersection of Warren and Miller Road and it is accepted as a careful and faithful perpetuation of the position of the original corner.

Witnesses:

N. 68° E., 61.20 feet Cut cross S.W. face of steel light pole base
S. 20° E., 63.26 feet Cut cross S.W. bolt of light pole base
S. 48° W., 77.87 feet Mag. nail and Wayne County Remon. tag N.W. face of U-pole
N. 13° W., 68.60 feet Cut cross on East bolt of fire hydrant

Signed by [Signature]

Date 12-16-99

Surveyor's Michigan License No. 37281

R LCR 9 4R 1Pg A DPL