

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located in: GREENFIELD TWP
(NOW CITY OF DETROIT) *Common Cor*

Corner Code # E-13
E-01 ✓

1. Public Land Survey T 1S R 11E
T 25 R 11E

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *ncd.*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on OCTOBER 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED 3, SEPT. 1816

PLATS

- L. 43 P. 95
- L. 51 P. 15
- L. 52 P. 86
- L. 52 P. 87

- ROBERT OAKMAN LAND CO. "BONAPARTE BOULEVARD SUBDIVISION"
- ROBERT OAKMAN LAND CO. "BONAPARTE AVE. & OAKMAN HIGHWAY SUB"
- ROBERT OAKMAN LAND CO. "WYOMING-OHIO SUBDIVISION"
- "ELLIS SUBDIVISION"

- OCTOBER 17, 1921
- OCTOBER 3, 1924
- MARCH 3, 1925
- MARCH 3, 1925

95 DEC - 8 PM 2:10
95263072
FORESTER: YOUNGELDOO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 T.1S, R.11E. COMMON TO E-1 T.2S, R.11E.

NO EVIDENCE OF CORNER FOUND

RE-ESTABLISHED NORTH LINE OF JOY ROAD USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMANS LAND COMPANY SUB" L. 52 P. 86. RE-ESTABLISHED EAST LINE OF WYOMING USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMAN'S LAND COMPANY SUB" L. 43 P. 95. VERIFIED LOCATION WITH STONE CURB SPLITS AND SIDEWALK SPLITS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

E-13 TO E-12 2643.32' (M.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

- AZ. 316° 59.74' SET PK NAIL AND W.C.R. TAG IN NORTHWEST FACE OF UTILITY POLE
- AZ. 198° 82.18' SET PK NAIL AND W.C.R. TAG IN SOUTHEAST FACE OF UTILITY POLE
- AZ. 152° 60.09' SET PK NAIL AND W.C.R. TAG IN EAST FACE OF UTILITY POLE
- AZ. 140° 60.71' SET PK NAIL AND W.C.R. TAG IN CONC. WALK

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408

4
7D
7D