

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

LI 27018 PA 407

Table with columns: (County), Located In, Corner Code ##. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column D and row 5.

I, George M. Platz, in a field survey on November 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5 CORNER COMMON TO SECTIONS 8, 9, 16, 17

GLO SURVEY PERFORMED BY JOSEPH FLETCHER IN THE EARLY 1800'S. THE ACTUAL DATE AND TYPE OF POST SET WAS NOT SPECIFIED.

CITY OF DEARBORN ENGINEERING RECORDS (FIELD BOOK NO. 1047, DATED 1934). TYPE OF POST RE-SET/FOUND WAS NOT SPECIFIED.

MDOT WITNESS CARD (DATED 1964) FOUND 5/8" IRON ROD IN MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 FOUND 1" IRON ROD IN MONUMENT BOX FROM ABOVE REMAINING ACCESSORIES. THROUGH THE ANALYSIS OF FIELD MEASUREMENTS MADE TO VARIOUS FOUND MONUMENTATION POINTS IN THE SOUTHEAST 1/4 OF SECTION 8, BY SPALDING, DEDECKER, THIS POINT APPEARS TO BE THE ONE OTHER SURVEYORS HAVE RELIED UPON IN THE PAST. NO SURVEY KNOWN, RECORDED OR UNRECORDED, HAS WITNESSES SHOWN FOR THIS POINT. THIS POINT FITS LOCAL EVIDENCE FOUND IN THE NORTHWEST 1/4 OF SECTION 16, 'SHEAHAN AND NAVIN'S SUBDIVISION'. (L19, P.60, RECORDED IN 1894) WITH A POSITIONAL TOLERANCE OF +/- 0.2' (SEE RESEARCH DOSSIER). ALL EXISTING KNOWN EVIDENCE ANALYZED FAVORS THE CORRECTNESS OF THIS POINT.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 CORNER COMMON TO SECTIONS 8, 9, 16, 17

FOUND 1 INCH IRON ROD IN MONUMENT BOX. SET 1/2' IRON ROD IN CONCRETE WITH WAYNE COUNTY REMONUMENTATION TAG AND LICENSE CAP #38121 DIRECTLY ABOVE 1" IRON ROD. THIS LOCATION IS ACCEPTED BY MYSELF AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

- AZ. 22°, 77.65'; SET PK NAIL WITH WCR TAG IN WEST FACE OF UTILITY POLE
AZ. 68°, 75.38'; SET PK NAIL WITH TAG #38121 IN SE FACE OF UTILITY POLE
AZ. 140°, 50.42'; NW CORNER BLDG. #5330
AZ. 150°, 51.76'; SET CUT "+" ON NORTH RIM OF STORM MANHOLE LOCATED IN CONCRETE SIDEWALK
AZ. 235°, 82.71'; FOUND PK NAIL IN NORTHWEST FACE OF UTILITY POLE
AZ. 303°, 98.85'; FOUND PK NAIL IN NORTHEAST FACE OF UTILITY POLE
AZ. 345°, 161.53'; SET PK NAIL WITH WCR TAG IN WEST FACE OF UTILITY POLE

93 DEC -8 PM 1:41
FORESTER, YOUNGBLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI



Signed by George M. Platz Date 12-3-93

Surveyor's Michigan License No. 38121