

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1571

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127800PA064

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 8:22 A.M. RECEIPT# 129
RECORDED
FOREST E. YOUNGLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

Wayne (County)	Located In:	Corner Code #
1. Public Land Survey	T 3 S R 8 E	G-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-8-94
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

RC 1571

I, William L. Roskelly, in a field survey on November 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-12) East Corner Section 33 T.3 S., R.8 E.

G.L.O. (1830's) J. Wampler set corner, witnesses W0 12 N.11 E.22 (gone), Ash 10 S.14 (gone)
W.P.A. (1930's) found an iron, witnesses: N.W. 36.01 40" Poplar (measured = 35.92),
W. 36.40 power pole (gone), E. 32.80 power pole (gone), N.E. 56.65 2" Elm (gone).
Wayne County Road Comm. 4/23/70 E. Johns found a monument in mon. box, witnesses:
N.W. 36.01 48" Poplar (measured = 35.92), N.W. 31.12 M.B.T. pole (gone),
S.E. 80.20 N.E. Building cor. #16416 (measured = 80.15), S.E. 35.59 14" Maple (gone).
No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-12) East Corner Section 33 T.3 S., R.8 E.

Found a steel bar concrete monument in a mon. box at Sumpter road.
Corner location supported by comparing W.P.A. survey with field measurements:
G-12 to G-11 W.P.A. = 2660.62 Measured = 2660.87
G-12 to G-13 W.P.A. = 2629.20 Measured = 2629.18
G-13 to H-13 W.P.A. = 2651.50 Measured = 2651.96
Angle line G-12 & G-11 to G-12 & H-13 W.P.A. 90° 34' 20" Measured = 90° 33' 56"
Angle line G-12 & G-11 to G-12 & G-13 W.P.A. 181° 03' 05" Measured = 181° 02' 21"
Corner also supported by Wayne County Road Comm. 4/23/70 E. Johns
N.W. 36.01 to 48" Poplar (now a 60" Poplar) Measured = S.60 W. 80.15
N.E. house corner, house #16416 Record = 36.01 Measured = N. 40 W. 35.92

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-12) East Corner Section 33 T.3 S., R.8 E.

Found a steel bar concrete monument in a mon. box at Sumpter road.
The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
Witnesses:

Set nail W.C.R. tag N.W. face 12" Elm N.32° E. Dist. = 77.72
Set nail W.C.R. tag N.E. face P. pole S.60° E. Dist. = 36.60
Set nail W.C.R. tag N.W. face 24" Poplar S.63° W. Dist. = 51.85
Set nail W.C.R. tag N.E. face 60" Poplar N.40° W. Dist. = 35.75
Placed Wayne County Remonumentation brass marker stamped with #10705

Signed by William L. Roskelly Date 12/27/94
Surveyor's Michigan License No. 10705

