

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

L127800PA068

Wayne (County) Located In: Corner Code # I-3
1. Public Land Survey T 3 S R 8 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

RC 1574

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 3.

I, William L. Roskelly, in a field survey on October 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3) Section Corner Common to Sections 2,3,10 & 11, T.3 S.,R.8 E.

G.L.O. (1830's) J. Wampler set post, no witnesses in notes.
W.P.A. (1930's) found an iron, witnesses N.W. 40.98 16" Maple (gone)
S.W. 38.35 W.C.R. sign (gone), S.E. 39.41 30" Elm (gone)
W.C.R.C. 6/4/70 E. Johns monument with box witnesses
N.W. 50.53 M.B.T. pole (found M.=50.43), N.E. 45.17 D.E. pole (found M.=44.88), N.E. 93.76 Top/Center hydrant. (not verified)
No R.C.'s or C.S.'s found at Wayne County Reg. of Deeds.

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 8:22 A.M. RECEIPT# 128
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3) Section Corner Common to Sections 2,3, 10 & 11, T.3 S.,R.8 E.

Found a monument box with steel bar in concrete at the intersection of Ecorse and Morton Taylor Roads. Compared field measurements to W.P.A. survey.

I-2 to I-3 W.P.A. = 2685.44 Measured = 2685.98
I-3 to H-3 W.P.A. = 2690.42 Measured = 2690.97
I-3 to J-3 W.P.A. = 2812.67 Measured = 2812.85

Line I-3 to I-2 - I3 to H3 W.P.A. = 90° 54' 20" Measured = 90° 51' 11"
Line I-3 to I-2 - I3 to J3 W.P.A. = 89° 23' 00" Measured = 89° 23' 35"

Found W.C.R.C. tag on the West face of a power pole W.C.R.C. N.E. 45.17 measured 44.88
Found W.C.R.C. tag on M.B.T. pole W.C.R.C. N.W. 50.53 measured 50.43

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3) Section Corner Common to Sections 2,3, 10 & 11, T.3 S.,R.8 E.

Found a monument box with steel bar in concrete at the intersection of Ecorse and Morton Taylor Roads.

Found nail W.C.R.C. tag W face P. pole N.50° E dist: 44.88
Set nail WCR tag NE face 8" Maple S.30° E dist: 129.91
Found center top of utility box: S.50° W dist: 57.30
Found nail W.C.R.C. tag E. face guy pole N.40° W dist: 50.43
Placed Wayne County Remonumentation brass marker stamped with #10705

2 R
11 D
MISC

Signed by [Signature]
Surveyor's Michigan License No. 10705

Date 12/27/94

