

FEB 28 2000

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Liber-30845 Page-17
99592652 12/28/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

<u>Wayne, Van Buren Twp.</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S.</u> R <u>8E.</u>	<u>I-10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 9, 1999

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William L. Roskelly, in a field survey on Nov 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10) East corner section 27, T.3 S., R.8 E., Van Buren Township
G.L.O. (1830's) J Wampler set corner post, witnesses: RO 5 N61 W6, Ash 6 N84 E 8
W.P.A. (1930's) stone, witnesses: NE 34.08' fence post (gone), SE 123.81' 20" Apple (gone), SW 96.40' 16" Elm (gone), NW 44.94' 6" Elm (gone), WCRC 4/27/70 E. Johns found iron, witnesses: SE 57.81' Wolverine Oil Line concrete marker (meas. S31@07'29"E 58.67'), SW 52.51' Wolverine Oil Line concrete marker (meas. S36@42'34"W 52.53'), SW 27.34' MBT pole (gone), SW 33.00' iron (gone).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10) East corner section 27, T.3 S., R.8 E., Van Buren Township
Found an iron pipe 1' below gravel road surface (Martinsville Road).
Verified corner location by comparing W.P.A. data with field measurements:
I-10 to I-9 Record = 2674.96' Measured = 2674.30' I-10 to I-11 Record = 2686.73' Measured = 2686.64'
Angle line I-10 & I-9 to I-10 & I-11 Record = 172@06'05" Measured = 172@04'49"
WCRC 4/27/70 E. Johns witnesses: SE 57.81' Wolverine Oil Line concrete marker (meas. S31@07'29"E 58.67'), SW 52.51' Wolverine Oil Line concrete marker (meas. S36@42'34"W 52.53')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10) East corner section 27, T.3 S., R.8 E., Van Buren Township
Set monument 6" below gravel road surface (Martinsville Road).
The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the corner. WITNESSES: NW corner mailbox pillar N53@29'42"E 35.76', found steel bar S82@28'08"E. 33.28', found Wolverine Oil Line concrete marker S31@07'29"E 58.67', found Wolverine Oil Line concrete marker S36@42'34"W 52.53', set nail and WCR tag S face power pole N81@55'35" W. 33.13', set steel bar cap #10705 N45@20'50" W. 40.44'.
Set nail and Wayne County Remonumentation tag and B&S #10705 in iron pipe.

Signed by William L. Roskelly
Surveyor's Michigan License No. 10705

Date 12-28-99



R LCR 9 4R 1Pg A 202