

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne

(County)

Located In: Van Buren Corner Code #

- 1. Public Land Survey T 3S. R 8E. K-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

LIBER 28471 PAGE 682

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-95 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

95271398

William Roskelly, in a field survey on December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column M and row 10.

A. Description of original monument and accessories and/or subsequent restoration:

K-10) East corner section 26, T.3 S, R.8 E., Van Buren Township

G.L.O. (1830's) J. Wampler set post, witnesses: Sugar 5 S 24 W 20 (gone), Do 5 N 67 W 22 (gone). W.P.A. (1930's) found an iron, witnesses: NW 33.41 fence post (gone), NE 35.20 4" Elm (gone), SE 61.25 16" Maple (gone), SW 33.47 F. post (gone), W.C.R.C. (4/27/70) E. Johns found an iron witnesses: NW 33.00 iron (not found), SE 57.81 Wolverine oil line markers (gone), SW 52.51 Wolverine oil line markers (gone), SW 27.34 M.B.T. pole (gone). CS 1708 (8/23/80) Daniel Sandomierski found a 1/4" re-rod witnesses: N. 34.42 SW corner cyclone fence (measured = 34.30), S 33° W 57.63 P.K. nail NW side of a 24" tree (measured = 57.60 +/-), S 4° E 46.99 P.K. nail NE side 18" tree (gone), S 49° E 43.41 P.K. nail NE side 18" tree (gone).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10) East corner section 26, T.3 S, R.8 E., Van Buren Township

Found an iron pipe Savage Road and West property line of house #41366. Verified the position of the corner by comparing W.P.A. survey with field measurements: K-10 to K-9 Record = 2677.15 Measured = 2676.96 K-10 to L-10 Record = 2736.16 Measured = 2736.81 K-10 to K-11 Record = 2661.03 Measured = 2660.86 Angle line K-10 and K-9 and L-10 Record = 92° 11' 20" Measured = 92° 09' 11" Angle line K-10 and L-10 to K-10 and K-11 Record = 87° 34' 10" Measured = 87° 36' 46" Angle line K-10 and K-11 to K-10 to K-9 Record = 180° 14' 30" Measured = 180° 14' 03" Also checked to the following witnesses from CS 1708: Found stump (tree gone) S. 33° W. 57.63 Measured = 57.60 +/- Found top post chain link fence N. 34.42 Measured = 34.30

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10) East corner section 26, T.3 S, R.8 E., Van Buren Township

Found an iron pipe Savage Road and West property line of house #41366. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

WITNESSES:

Found top post chain link fence post due North 34.42 (measured = 34.30) Set nail and WCR tag S.E. face 24" Maple N. 38° E. distance = 89.23 Set nail and WCR tag N.E. face P. pole S. 44° E. distance = 43.18 Found P.K. nail N.E. face P. pole S. 44° E. distance = 43.17 Found P.K. and washer E. face 29" Box Elder due South distance = 47.10 Set nail and WCR tag N.W. face 30" Ash S. 59° W. distance = 77.91 Placed Wayne County Remonumentation brass marker and cap #10705



Signed by [Signature] Date 12-14-95 Surveyor's Michigan License No. 10705

4R 7A D1