

**SURVEY & REMONUMENTATION**

**RC 1578**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING  
 28 DEC 94 8:23 A.M. RECEIPT# 128  
 RECORDED  
 FOREST E. YOUNGLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

**COMMISSION**

For corners in

Wayne  
 (County)

Located In:

Corner Code #

- 1. Public Land Survey      T 3 S R 8 E      M-2
- T     R
- T     R
- T     R
- 2. Property Controlling    S     T     R
- in Section                S     T     R
- 3. Miscellaneous            S     T     R
- Property in Sec.         S     T     R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

L'27800PA075  
 Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 12-8-94 *DPJ*  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1578

I, William L Roskelly in a field survey on November 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-2) East Corner Section 1 T.3 S.,R.8 E.

G.L.O. (1830's) J. Wampler set corner, no witnesses (no timber near corner).  
 W.P.A. (1930's) set an iron, witnesses: N.W. 25.15 fence post (gone), N.E. 751 +/- iron (not found), S.E. 36.49 Ed. pole (gone) S.E. 64.44 6" Elm (gone).  
 L.C.R.C. L.24985, P.525 R.C. #994 12/19/90 Robert J. Patterson found a 1/2" re-rod in a hand hole at Hannan and Ecorse Roads, witnesses:  
 N.25 E. 159.28 P.K. nail in U. pole (M. = 159.30), S.40 E. 87.20 W.C.R.C. nail & washer (gone), W. 33.72 P.K. nail in fence post (gone), S.75 E. 118.08 W.C.R.C. nail & washer (gone)  
 No C.S. on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2) East Corner Section 1 T.3 S.,R.8 E.

Found a steel bar in a monument box in the centerline of Hannan Road. Corner location supported by comparing W.P.A. survey with field measurements:  
 M-2 to M-1 Record = 3226.25 Measured = 3226.38  
 M-2 to M-3 Record = 2669.57 Measured = 2669.40  
 M-2 North to a conc. mon. in mon. box Record = 750.41 Measured = 750.48  
 Angle M-2 sight M-1 to M-2 turn to M-3 Record = 182° 37' 40" Measured = 182° 37' 39"  
 Corner also supported by:  
 Found P.K. & WCRC tag West face P. pole N.25° E. Record = 159.28 Measured = 159.30

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2) East Corner Section 1 T.3 S.,R.8 E.

Found a steel bar in a monument box in the centerline of Hannan Road. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.  
 Witnesses: Found P.K. & WCRC tag West face P. pole N.12° E. dist. = 159.30  
 Set nail & WCR tag in Conc. walk due West dist. = 53.74  
 Set nail & WCR tag S.W. face P. pole S.18° E. dist. 89.49  
 Set nail & WCR tag East face P. pole N.18° W. dist. 116.61  
 Center of sanitary MH N.15° W. dist. = 136.70

*ZR  
 11-D  
 MISC*

Placed Wayne County Remonumentation brass marker stamped with cap #10705

Signed by *William L Roskelly* Date 12/27/94  
 Surveyor's Michigan License No. \_\_\_\_\_

