

FEB 28 1994

RC 1337

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

WAYNE

County:

ROMULUS TOWNSHIP #13

Located in:

Corner Code #

- | | | | | |
|------------------------------------|---------|--------------|--------------|-------------|
| 1. Public Land Survey | | T <u>3 S</u> | R <u>9 E</u> | <u>B-03</u> |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth S. Wilkerson, in a field survey on October 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-03 Set Post - GLO - NO GLO WITNESSES REMAIN
Fd. Iron - B of T
Fd. mon. in mon. box, L. 21149, P. 546 - 05/20/77

N 20 W 66.75 nail in SW face MBT P
S 45 W 75.74 spike in NW face MBT P
S 20 E 62.69 spike in W face MBT P
N 60 E 70.57 spike in NW face PP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-03 Fd. 1/2" rod in mon. box
Matches ties of L. 21149, P. 546

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set WC remonumentation washer and OHM KSW 21584 cap on iron.

B-03 N 52 E PK in PP
S 22 W 77.58 WCRC tag in UP
S 40 W 75.69 WCRC tag in UP
N 70 W 110.05 PK in UP
E 0.79 nail in S face FP
S 83.25 nail in W face MBT P

The selected location is accepted as the best evidence of the original corner.

Signed by: *Kenneth S. Wilkerson*

Date: Nov 30 1993

Drafted By: Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.
34935 Schoolcraft Road * Livonia, Michigan 48150 * Phone: (313) 522-6711

LI 27042 PA 359

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE


Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4												
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RC 1337

FOREST COUNTY REGISTERED DEEDS
MICHIGAN STATE BOARD OF LAND SURVEYORS

DEC 15 PM 5:00



22
11K1