

FEB 23 1994

RC 1366

LI 27059 PA 140

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE COUNTY (County) Located In: Corner Code --#
1. Public Land Survey T 3S R 9E I2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-21-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, RAPHAEL LANDINI, in a field survey on DECEMBER 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. ELM 12 S47W 6 (4.0) (GONE)
LYNN 9 N36W 4 (2.6) (GONE)
WPA (1930S) STONE 15" ELM NE 38.40 (GONE)
WCRC SIGN POST SE 83.32 (GONE)
ED POLE SE 60.70 (GONE)
TEL POLE SW 42.75 (GONE)
FENCE POST NW 47.20 (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- WAYNE COUNTY ROAD COMMISSION 1971 POINT NOT IDENTIFIED
ED POLE NE 44.75 (MEAS. 44.76)
TWIN MAPLES SE 66.69 (GONE)
MBT POLE SW 41.33 (GONE)
TOP HYDRANT NW 53.53 (GONE)
WAYNE COUNTY DPS ROAD 1988 1/2" IRON IN MON BOX
WCRC TAG DE POLE NE 44.76 (MEAS. 44.76)
WCRC TAG DE POLE SE 86.23 (GONE)
WCRC TAG MBT POLE SE 44.05 (GONE)
WCRC TAG DE POLE NW 75.55 (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2 T-3 S, R.9.E.
SET STANDARD 4" DIA X 36" CONC. MON WITH 3/8" IRON ROD; REMON. BRASS DISK WITH CAP RJL RLS 16933 IN MON. BOX SELECTED LOCATION IS ACCEPTED BY CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDNECE OF THE POSITION OF THE ORIGINAL CORNER.
FOUND WCRC TAG N. FACE DE POLE N58°E 44.76
SET WCRC TAG NE FACE TRAFFIC POLE S38°E 56.11
SET CHISLED + ON CORNER OF KEY FLAG S74°W 69.39
SET WCRC TAG NE FACE OF DE POLE N50°W 67.08

Grid table with columns A-M and rows 2-13. A dot is present in cell H3.

93 DEC 22 AM 10:20
FORESTER YOUNGBLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI



Signed by Raphael J Landini Date DECEMBER 16, 1993
Surveyor's Michigan License No. 16933

Handwritten initials: 2L 111C D