

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

J-09 Page 1

For corners in
Wayne
County

Located in: Romulus Corner Code

L129366 PA 879

1. Public Land Survey		T <u>3</u> S R <u>9</u> E	<u>J-09</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-16-96 *DFJ*
**WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE**

Register of Deeds Stamp and File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth S. Wilkerson in a field survey on 02/15/1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

01/01/1816 G.L.O. Set Post
 9" Lynn N47W 6 links (gone)
 9" Hickory S7W 7 links (gone)

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" iron in mon. box . on Eureka Road (asph). Dist to I-9=2647.92'(R) in airport, K-9=2656.84'(R) 2656.77'(M), Donnelly 2656.69'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

02/15/1996 Wilkerson 21584 O.H.M. Remon

- SET W.C.R. CAP AND WASHER OVER FD. 1/2" I.P.
- S17W 25.32' to cl of C.B..
- 6 N85E 278.28' set W.C.R. tag in s. side of pole
- 7 S85E 277.28" set tag in S. side pole
- 8 N89W 329.83' To hyd.
- 9 S17W 25.32' to cl of C.B..

\$ 10.00 DEED
 30 DEC 96 1:36 P.M. RECEIPT# 44B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by *Kenneth S. Wilkerson* Date Dec 16 1996
 Drafted by Kenneth S. Wilkerson
 Surveyor's Michigan License No. 21584

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150



4
10.
DFJ

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1932	W.C.R.C.	Not described
1	North 87.00' Steel Fence Post (gone)	
2	SE 53.30' Fen. post (gone)	
3	SW 32.50' SW Cor. (gone)	
4	SW 64.79' Fen. Post (gone)	
5	NW 34.48' Tile (gone)	
06/30/1970	W.C.R.C	Mon in mon. box
1	MBT pole north 34.90' (gone)	
2	iron south 33.00' (gone)	
3	guy pole sw 32.28' (gone)	
03/07/1990	Donnelly 21563 967	Fd. mon in mon. box
10	AZ 53 140.28' CHAIN LINK FENCE CORNER (gone)	
11	AZ 61 123.69' CL TOP OF HYD. (gone)	
12	175 42.33' NAIL WITH WCRC TAG TWIN 6" TREE (gone)	
13	AZ 314 132.92' SE CORNER OF BUILD #A30444 (gone)	