

Survey & Remonumentation

# RC 1350

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

## LI 27042 PA 372

For corners in

WAYNE

County:

ROMULUS TOWNSHIP #13

Located in:

Corner Code #

- |                                       |         |              |              |             |
|---------------------------------------|---------|--------------|--------------|-------------|
| 1. Public Land Survey                 |         | T <u>3 S</u> | R <u>9 E</u> | <u>L-03</u> |
|                                       |         | T _____      | R _____      | _____       |
|                                       |         | T _____      | R _____      | _____       |
|                                       |         | T _____      | R _____      | _____       |
| 2. Property Controlling<br>in Section | S _____ | T _____      | R _____      | _____       |
|                                       | S _____ | T _____      | R _____      | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ | T _____      | R _____      | _____       |
|                                       | S _____ | T _____      | R _____      | _____       |

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 *XBJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Kenneth S. Wilkerson, in a field survey on October 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-03 Set Post - GLO - NO GLO WITNESSES REMAIN  
Fd. Iron Pipe - B of T
- Fd. Mon. in Mon. box, L. 20402, P. 909 - 10/27/77
- NE 85.64 nail in SE face 5" cherry  
NE 128.77 nail in NW face PP  
SE 34.81 nail in E face 4" cherry  
NW 47.13 nail in SW face PP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-03 Fd. 1/2" rod in mon. box
- S 63 E 40.60 St sign  
S 27 W 80.80 X on N rim San MH  
S 36 W 65.41 reroed in E face PP  
N 43 W 45.15 PK in S face PP  
N 6 W 50.60 top nut on hyd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set WC remonumentation washer and OHM KSW 21584 cap on iron.
- L-03 N 50.72 top nut on hyd  
S 23 E 101.44 OHM tag in NE face UP  
S 40 W 65.52 WCRC tag in NW face UP  
N 35 W 45.10 OHM tag in NE face UP

The selected location is accepted as the best evidence of the original corner.

Signed by: *Kenneth S. Wilkerson*


Date: Nov 30 1993

Drafted By: Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.  
34935 Schoolcraft Road \* Livonia, Michigan 48150 \* Phone: (313) 522-6711

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

93 DEC 15 PM 5:00  
FOREST E. YOUNGBLOOD  
REGISTER OF DEEDS  
WAYNE COUNTY, MI



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

*2R  
11KD*