

RC 1351

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LI27042PA373

For corners in

WAYNE  
County:  
ROMULUS TOWNSHIP #13

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 3 S R 9 E L-07  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 *POJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1351

I, Kenneth S. Wilkerson, in a field survey on October 28, 19 93  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land Management  
or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in  
conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;  
established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-07 Set Post - GLO - NO GLO WITNESSES REMAIN  
Fd. Iron - B of T

L-07 Fd. Conc. Mon., L. 19461, P. 536 - 05/01/76

N 45 E 42.13 rd. sign  
S 30 W 61.38 PK in MBT P  
N 23 W 68.01 PK in SW face PP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-07 Fd. 1/2" rod in mon. box

NE 80.16 nail in a GP  
SW 61.18 nail in GP  
NW 68.12 nail in PP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set WC remonumentation washer and OHM KSW 21584 cap on iron.

L-07 N 15 E 181.76 OHM tag in NW face PP  
S 33 E 113.62 NW cor building  
S 30 W 64.81 OHM tag in NW face PP  
N 45 W 67.85 OHM tag in SW face PP


The selected location is accepted as the best evidence of the original corner.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

93 DEC 15 PM 5:00  
FOREST & YOUNGBLOOD  
REGISTER OF DEEDS  
WAYNE COUNTY MI

Signed by: *Kenneth S. Wilkerson*

Date: Nov 30 1993



Drafted By: Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983

Orchard, Hiltz & McCliment, Inc.  
34935 Schoolcraft Road \* Livonia, Michigan 48150 \* Phone: (313) 522-6711

*2R  
11KD*