

SURVEY & REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APR 05 1996

L-09 Page 1

For corners in

Wayne COMMISSION Located in: Romulus Corner Code

LIBER 28647 PAGE 713

County

1. Public Land Survey	T	3	S	R	9	E	L-09
	T			R			
	T			R			
	T			R			
2. Property Controlling in Section	S			T			
	S			T			
3. Miscellaneous Property in Sec.	S			T			
	S			T			

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-30-95 [Signature] WAYNE COUNTY REMONUMENTATION BOARD GROUP COMMITTEE

Register of Deeds Stamp and File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth S. Wilkerson In a field survey on 11/03/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restorations:
  - 01/01/1816 G.L.O.
  - 9" W.O. S 61 E 1.25 LINKS (GONE)
  - 12" B.O. S 45 W 4.14 LINKS (GONE)

(Witnesses Continued on Back ...)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
  - 3/8" I.R. MON BOX DIST TO M9=2656.97(R) 2657.03(M) DIST TO K9=2652.44(R) 2652.57(M)
  - CORNER IN ASPHALT ROAD
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
  - 11/03/1995 Wilkerson 21584 O.H.M. Remon
  - SET W.C.R. REMON CAP AND WASHER OVER 3/8" I.R.
  - 8 TOP NUT HYD. S 56 E 55.65'
  - 9 W.C.R.C. NAIL AND TAG W FACE U.P. S 44 E 43.57'
  - 10 S.E. FACE U.P. O.H.M.K.S.W. TAG S 23 E 82.09'
  - 11 P.K. W FACE U.P. N 23 W 68.61'
  - 12 W FACE U.P. O.H.M. K.S.W. TAG N 25 E 73.34'

95273126  
96065626

96 MAR -7 AM 11:27  
FOREST E. YOUNGBLOOD



We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date Dec 8 1995  
Drafted by Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

RECORDED TO ADD PERM GROUP DATE

\$ 10.00 DEED  
21 DEC 95 9:21 A.M. RECEIPT# 5B  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

\$ 4.00 REMONUMENTATION

Handwritten notes: n/c per [Signature]

RECORDED

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1930

B/T

IRON

- 1 CULVERT NE 40.98' (GONE)
- 2 14" TWIN ELM 50.35' (GONE)
- 3 Ed POLE SW 81.96' (GONE)
- 4 CULVERT NW 41.59' (GONE)

LIBER 28477 PAGE 221

05/05/1970

KLOPSKINSKE

W.C.R.C.

MON. IN MON BOX

- 5 MBT SE 43.89' (GONE)
- 6 Ed. POLE NW 67.85' (GONE)
- 7 Ed POLE SW 81.94' (GONE)

LIBER 28647 PAGE 714