

SURVEY & RECONSTRUCTION

RC 1353

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127042PA375

For corners in

WAYNE
County:
ROMULUS TOWNSHIP #13

Located in:	Corner Code #
T 3 S R 9 E	L-13
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 *DRJ*

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Kenneth S. Wilkerson, in a field survey on September 30, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 Set Post - GLO - NO GLO WITNESSES REMAIN
Stone - B of T

Iron in mon. box - WCRC 05/01/70
Iron in mon. box, L. 18309, P. 733

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Fd. conc. mon. in mon. box

NE 131.38 WCRC tag in SE face PP - Fd.
S 80.23 WCRC tag in E face PP - Fd.
N 51.74 WCRC tag in E face PP - Fd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set WC remonumentation washer and OHM KSW 21584 cap on iron.

L-13 N 05 E 52.00 PK in E face PP
N 70 E 131.33 OHM tag in NW face PP
S 07 W 80.15 OHM tag in E face PP
N 75 W 176.81 Top nut on hyd.

The selected location is accepted as the best evidence of the original corner.

Signed by: *Kenneth S. Wilkerson*


Date: Nov 30 1993

Drafted By: Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.
34935 Schoolcraft Road * Livonia, Michigan 48150 * Phone: (313) 522-6711

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

93 DEC 15 PM 5:00
FOREST E. YOUNGBLOOD
REGISTER OF DEEDS
W. LANSING, MI



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

2R
11K1