

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wayne County Located in: Romulus Corner Code
1. Public Land Survey T 3 S R 9 E M-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-16-96
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp and File Number

Grid table with columns A-L and rows 2-13 containing numbers 1-36.

I, Kenneth S. Wilkerson in a field survey on 02/15/1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:
01/01/1816 G.L.O. Set post.
6" B.O. S. 66 W. 1.86 Links (gone)
12" B.O. N. 71 W. 1.74 Links (gone)

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Fd. 3/4" pipe in mon. box, dist to M-09 = 2655.07'(R) 2654.61'(M), McManon 2655.07' in 1944 and to M-11 = 2587.39'(R) 2587.47'(M) (Inkster Rd. - Asph)


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
02/15/1996 Wilkerson 21584 O.H.M. Remon

- Set WCR cap over fd. 3/4" I.P. (NOT A COMMON CORNER)
1 1/2" I.P. IN MON. BOX NORTH 89.22' (R&M)
6 S 40 E Fd. TAG IN DE POLE 39.50'
8 S 20 W Fd TAG ON E SIDE DE POLE 124.47'
9 N 10 W Fd. TAG IN E. SIDE DE POLE 150.50'
11 N 70 W Fd. PK S SIDE FENCE POST 74.70'
12 N 75 W SET TAG ON E FACE OF 24" TREE 48.70' (M) 49.42' (R)

\$ 10.00 DEED
30 DEC 96 2:34 P.M. RECEIPT# 578
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
\$ 4.00 REMONUMENTATION

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date DEC
Drafted by Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584
Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150



Handwritten notes: 4R, 100, DC

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1930		B/T		Iron
1	Iron N. 89.22' (R) 89.22' (M)			
2	36" Willow N.E. 109.61' (gone)			
3	Mon N.E. 36.91' (gone)			
4	24" Elm E. 21.55' (gone)			
5	Mon N.W. 137.93' (gone)			
05/05/1970	Klopskinske	W.C.R.C.		Iron
1	Iron N. 89.22' (R&M)			
6	M.B.T. S.E. 37.88' (gone)			
7	Corner of house 14085 S.E. 68.28' (gone)			
8	Ed. pole S.W. 124.47' (gone)			
9	Ed. pole N.W. 150.50' (R&M)			
03/25/1975	J. Canning	W.C.R.C.		1/2" mon in mon box
7	N.W. corner of house 14085 S.E. 68.20' (gone)			
8	W.C.R.C. tag in N side of pole S.E. 37.83' (gone)			
10	Tag N. side of 6" Maple N.W. 49.42' (R) 48.70'(M)			
11	Nail w/ tag N.E. of fp N.W. 74.82' (R) 74.70 (M)			
03/26/1975		W.C.R.C.		Fd iron
	SAME AS ABOVE			
09/29/1975	Wilkerson	21584	439	Fd. iron pipe in handhole
1	Mon box north 89.30'(R) 89.22' (M)			
7	nw cor. of house #14085 S60E 68.20' (gone)			
11	nail & cap NE side fp N60W 74.85' (R) 74.70' (M)			
13	conc. mon S60W 72.87'			

LI29367PA182