

FEB 28 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 27033 PA 898
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)	Located In: CITY OF TAYLOR	Corner Code --#
1. Public Land Survey	T 3S R 10E	B-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-30-93 DPL
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1306

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.
WITNESSES: W0 16" S 20 W 34 (22.44') (GONE)

W.P.A. (1930's) WITNESSES: 12" CHERRY NW 63.09
(IRON) #90 12" ELM NE 37.61
20" WILLOW SE 58.32
24" WILLOW S 24.52

L.C.R.C. N 86 L.18112 P.372 (6-15-72)
CS #1283 L.19645 P.760-762 (11-16-72)

93 DEC 13 PM 5:29
FORREST...
REGISTER OF DEEDS
WAYNE COUNTY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO A7 MEASURED AS 2606.28'; RECORDED 1930 W.P.A. DISTANCES OF 2606.03' AND 2606.00';
DISTANCE TO C7 MEASURED AS 2618.65'; RECORDED 1930 W.P.A. DISTANCES OF 2618.03' AND 2617.61';
L.19645 P.762 - FOUND MON. BOX IN PAVEMENT (1972)
N 35° E 54.05' C/L SEWER M.H. (54.12' MEAS.)
S 20° W 47.33' C/L WAYNE COUNTY WATER M.H. (47.33' MEAS.)
N 25° W 56.00' C/L SEWER M.H. (56.07' MEAS.)
L.18112 P.372 - FOUND IRON IN HANDHOLE (1972)
NW'LY 50.69' CROSS CUT IN 6" CURB (GONE)
NE'LY 67.96' CROSS IN LAMP POST (MEAS. 69.00')
SE'LY 55.15' TOP NUT IN HYDRANT (MEAS. 55.16')
SW'LY 41.15' CROSS IN LAMP POST (MEAS. 40.93')
(NO OTHER L.C.R.C. RECORDS AT WAYNE COUNTY REGISTER OF DEEDS)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 SECTION CORNER 18 & 19, T3S, R10E
FOUND A CONCRETE MONUMENT IN A HANDHOLE ROAD BOX AT GODDARD AND HOLLAND ROADS AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 56°18'E 68.00' FOUND CHISELED "X" IN SW ANCHOR BOLT IN BASE OF STEEL LIGHT POLE (SUPRA)
S 20°26'E 55.16' FOUND C/L TOP BOLT IN FIRE HYDRANT (SUPRA)
S 29°07'W 40.93' FOUND CHISELED "X" IN NE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE (SUPRA)
N 64°09'W 59.70' (SET) SOUTHEAST CORNER TO RIM OF CATCH BASIN

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND MONUMENT B-7.

Signed by Edward P. O'Rourke
Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993

2R
11K D