

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

WAYNE _____
(County)

Located In: Corner Code #

CITY OF TAYLOR TWP. #14

- | | | | |
|------------------------------------|------|-------|------|
| 1. Public Land Survey | T 3S | R 10E | B-13 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LI27797PA660

RC 1506

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *JBL*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

RC 1506

Register of Deeds Stamp & File Number

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
WITNESSES: WO 9 N 63 W 11 (7.26') (GONE)
POPLE 9 N 11 E 31 (20.46") (GONE)

RESURVEY AT DIRECTION OF ALBERT CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
WPA (1930's) - CROSS ON STONE (S 31) #168
WITNESSES: E'LY 14.35 IRON N-6 BROWNSTOWN TWP. (MEAS. 14.47')
NO OTHER WITNESSES FOR B-13 WERE NOTED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON ROD IN HANDHOLE ROAD BOX (NO LID) IN PENNSYLVANIA ROAD
DISTANCE TO A-13 MEASURED AS 2612.58; RECORD WPA (1930) DISTANCE OF 2612.58
DISTANCE TO C-13 MEASURED AS 2612.22; RECORD WPA (1930) DISTANCE OF 2612.19
EAST 14.47' IRON IN ROAD BOX.

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 SECTION CORNER SOUTH OF 31, T.3S, R.10E.
3/8" IRON ROD IN HANDHOLE ROAD BOX ON PENNSYLVANIA ROAD, A TWO LANE ASPHALT SURFACE ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: S 47°23' E 55.72' SET CUT "X" ON WEST RIM OF A GATE VALVE AND WELL
S 53°07' E 58.68' CENTERLINE TOP BOLT ON FIRE HYDRANT
N 38°24' W 42.18' SET CUT "X" ON SOUTHWEST RIM OF A GATE VALVE AND WELL
N 03°25' W 51.40' FOUND A PK/FLASHER ON EAST SIDE OF A UTILITY POLE
EAST 14.47' FOUND IRON IN ROAD BOX

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE FOUND IRON ROD B-13.

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

