

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located in: CITY OF TAYLOR TOWNSHIP #14	Corner Code # D-11
1. Public Land Survey	T <u>3S</u> R <u>10E</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 29337 PAGE 548

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-13-96

**WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE**

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32								
13											

I, WALTER J. ZBIKOWSKI, in a field survey on SEPTEMBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. (1815-1817)
 G.L.O. (1817) WEST ON TRUE LINE BETWEEN SEC 29-32, 39.96-1/2 CHAINS, SET 1/4 SEC. COR. AVG. DIST.
 (DISTANCE OF CORNER NOT STATED IN NOTES)

WITNESSES: W.O. 9" N 64 W 93 (LINKS) (61.38') (GONE)
 POPE 10" N 11 E 1.30 (LINKS) (0.86') (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

W.P.A. (1930's), IRON, N-33 (#140)

WITNESSES: NNE 43.61' TELEPHONE POLE (GONE)
 ENE 30.96' MON. (GONE)
 SE 77.69' TELEPHONE POLE (GONE)
 NW 29.93' MON. (GONE)

12 DEC 96 2:11 P.M. RECEIPT# 62D
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

FOUND A 1/2" IRON PIPE/MONUMENT IN A ROAD BOX (GOOD) IN THE CENTER LANE OF EUREKA ROAD (A FIVE LANE CONCRETE PAVEMENT) AT WESTLAKE ROAD (A VARIABLE SIZE CONCRETE PAVEMENT)
 DISTANCE TO E-11 TRAVERSED AS 2643.41'; G.L.O. (1817) RECORD DISTANCE OF 39.96-1/2 CHAINS (2637.69'); "PATTERSON'S HOME TRACTS SUB" L.52 P.11 (1924) RECORD DISTANCE OF 2637.30'; W.P.A. (1930's) RECORD DISTANCES OF 2643.84' AND 2644.06';

DISTANCE TO C-11 TRAVERSED AS 2639.63'; G.L.O. (1817) RECORD DISTANCE OF 39.96-1/2 CHAINS (2637.69'); W.P.A. (1930's) RECORD DISTANCES OF 2639.48' AND 2639.76';

L.18209 P.690, FOUND IRON ROD IN MONUMENT BOX (1972) LCRC #137

WITNESSES: N.60°E. 74.2' FIRE HYDRANT (MEASURED 74.08')
 S.50°E. 47.3' DETROIT EDISON POLE (RELOCATED)
 S.25°W. 89.4' SIGN POST (RELOCATED)
 N.45°W. 57.6' DETROIT EDISON POLE (MEASURED 57.41')

L.19026 P.900, CONCRETE MONUMENT IN BOX REPLACES EXISTING CONCRETE MONUMENT IN BOX (1975) LCRC #399

WITNESSES: NE 82.30' "X" CUT IN WEST SIDE OF STEEL SIGN POST (GONE)
 SE 54.29' SPIKE WITH BRASS TAG IN WEST SIDE OF MICHIGAN BELL POLE (GONE)
 SW 67.50' "X" CUT IN KEY SIDEWALK FLAG AT SOUTHWEST COR EUREKA AT WESTLAKE (GONE)
 NW 56.96' SPIKE WITH BRASS TAG IN EAST SIDE OF DETROIT EDISON POLE (GONE)

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
 D-11, SECTION CORNER 29, 32 T.3S., R.10E.

PLACED A BRASS REMONUMENTATION DISC AND PVC CAP #21586 ON 1/2" IRON PIPE/CONCRETE MONUMENT IN A ROAD BOX IN THE CENTER LANE OF EUREKA ROAD (A FIVE LANE CONCRETE PAVEMENT) AT WESTLAKE ROAD (A VARIABLE SIZE CONCRETE PAVEMENT) AND IT IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N.34°58'E. 54.91' FOUND "X" CUT IN SOUTHEAST BOLT IN BASE OF A STEEL LIGHT POLE (SUPRA)
 S.41°56'E. 54.68' FOUND PK NAIL ON SOUTHWEST SIDE OF A UTILITY POLE (SUPRA)
 S.56°29'W. 86.02' FOUND "X" CUT IN SOUTHEAST BOLT IN BASE OF A STEEL LIGHT POLE (SUPRA)
 N.40°22'W. 57.32' FOUND PK NAIL ON EAST SIDE OF A UTILITY POLE (SUPRA)

Signed by Walter J. Zbikowski Date DEC. 11, 1996
 Surveyor's Michigan License No. 21586

410
100
m

B. CONTINUED

LIBER 29337 PAGE 549

L.25437 P.672, FOUND MONUMENT IN ROAD BOX (1991) LCRC #1022

WITNESSES: N.37°31'E. 54.98' TO "X" CUT IN SOUTHEAST BOLT IN BASE OF STEEL LIGHT POLE (MEASURED 54.91')
S.39°37'E. 54.79' TO A PK NAIL ON THE WEST SIDE OF A UTILITY POLE (MEASURED 54.68')
S.58°59'W. 86.05' TO "X" CUT IN SOUTHEAST BOLT IN BASE OF A STEEL LIGHT POLE (MEASURED 86.02')
N.37°50'W. 57.31' TO A PK NAIL ON THE EAST SIDE OF A UTILITY POLE (MEASURED 57.32')

FILE DO NOT MAIL