

SURVEY & REMONUMENTATION

APR 25 1995

RC 1507

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA661

For corners in

WAYNE _____ (County)	Located In: CITY OF TAYLOR TWP #14	Corner Code #: D-13
1. Public Land Survey	T 3S R 10E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-27-94 *DRJ*
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

RC 1507

Register of Deeds Stamp & File Number

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
WITNESSES: POPE 9 S 6 E 65 (42.90' R) (GONE)
DO 9 N 71 E 92 (60.72' R) (GONE)
RESURVEY AT DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
W.P.A. (1930's) STAKE OVER STONE (S-32) #166

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:04 A.M. RECEIPT # 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND A 1/2" IRON PIPE IN CONCRETE MONUMENT IN ROAD BOX (NO LID).
DISTANCE TO C-13 MEASURED AS 2668.01'; RECORD W.P.A. (1930) DISTANCES OF 2667.43' AND 2667.64'
DISTANCE TO E-13 MEASURED AS 2644.54'; RECORD W.P.A. (1930) DISTANCES OF 2644.49' AND 2644.84'
L.19606 P.714-716 NO DESCRIPTION OF CORNER ON RECORD (1976)
S 16° W 54.24' NAIL IN DETROIT EDISON POLE (MEASURED 54.31')
N 74° W 182.12' NAIL IN DETROIT EDISON POLE (MEASURED 182.09')
N 60° W 58.52' CENTER OF FIRE HYDRANT (MEASURED 58.72')
L.20371 P.460 FOUND IRON IN MONUMENT BOX (1978)
S 20° W 54.53' NAIL AND CAP ON WOOD POLE (MEASURED 54.31')
N 46° W 58.75' TOP BOLT ON HYDRANT (MEASURED 58.72')
N 30° W 30.83' NAIL AND CAP ON WOOD POLE (GONE)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13 SECTION CORNER SOUTH 32, T.3S, R.10E
FOUND A 1/2" IRON PIPE IN CONCRETE MONUMENT IN ROAD BOX (NO LID) AND IN CENTER OF EAST BOUND LANE IN PENNSYLVANIA ROAD, A TWO LANE CONCRETE PAVEMENT ROAD, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
S 63°38' E 97.60 SET NAIL WITH SHINER ON NORTHEAST SIDE OF 12" FRUIT TREE
S 11°16' W 54.31 FOUND PK NAIL WITH BRASS TAG ON EAST SIDE OF UTILITY POLE (SUPRA)
N 46°00' W 58.72 CENTER OF TOP BOLT IN FIRE HYDRANT (SUPRA)
N 26°32' W 50.58 FOUND PK NAIL WITH BRASS TAG ON EAST SIDE OF UTILITY POLE

*21
14
M.S.*

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE 1/2" IRON PIPE/MONUMENT D-13.

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

Y001

L127797PA662

SECTION A (CONTINUED)

WITNESSES: NE 63.20 EDISON POLE (GONE)
SE 43.48 14" MAPLE (GONE)
SE 28.45 18" MAPLE (GONE)
NW 120.35 LOCUST TREE (GONE)
NW 87.10 EDISON POLE (GONE)