

**SURVEY & REMONUMENTATION**

**RC 1508**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**L127797PA663**

For corners in

<u>WAYNE</u> (County)	Located in:	Corner Code #
	CITY OF TAYLOR TWP. #14	
1. Public Land Survey	T <u>3S</u> R <u>10E</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
 ACT 345, P.A. 1990  
**APPROVED ON: 12-7-94**  
**WAYNE COUNTY REMONUMENTATION**  
**PEER GROUP COMMITTEE**

Register of Deeds Stamp & File Number

**RC 1508**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817  
 G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.  
 WITNESSES: POPE 10 N 29 E 36 (23.76') (GONE)  
 W.O. 6 N 84 W 25 (16.50') (GONE)  
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION  
 W.P.A. (1930's) IRON (NW 21) #87

(CONTINUED ON BACK)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND A 3/4" IRON IN CONCRETE IN A HANDHOLE ROAD BOX (NO LID) AT NORTHBOUND TELEGRAPH AND GODDARD ROADS.  
 DISTANCE TO D-7 TRAVERSED AS 2629.38'; RECORD W.P.A. (1930) DISTANCES OF 2627.57' AND 2628.62'  
 DISTANCE TO E-6 TRAVERSED AS 2634.50'; RECORD W.P.A. (1930) DISTANCES OF 2634.15' AND 2634.43'  
 DISTANCE TO F-7 TRAVERSED AS 2666.09'; RECORD W.P.A. (1930) DISTANCES OF 2665.75' AND 2665.91'  
 L.22794 P.793 FOUND RE-ROD IN MONUMENT BOX (1986)  
 N 50°50' E 80.46' TO CENTERLINE SOUTHWEST BOLT IN BASE OF STREET LIGHT POLE (MEAS. 80.56')  
 S 68°25' E 107.88' TO CENTERLINE NORTHWEST BOLT IN BASE OF STREET LIGHT POLE (GONE)  
 S 27°46' E 88.84' TO CENTERLINE NORTHWEST BOLT IN BASE OF LAMP POST (MEAS. 88.86')  
 S 48°58' W 81.44' TO PK NAIL SOUTHEAST (NORTHWEST) SIDE DETROIT EDISON GUY POLE (MEAS. 81.56')  
 N 48°11' W 72.20' TO PK NAIL SOUTHWEST (NORTHEAST) SIDE DETROIT EDISON POLE (MEAS. 72.20')

MISCELLANEOUS RECORDING  
 27 DEC 94 11:04 A.M. RECEIPT# 48A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-7 SECTION CORNER 16, 17, 20, AND 21, T.3S, R.10E  
~~FOUND~~ A 3/4" IRON IN CONCRETE IN A HANDHOLE ROAD BOX (NO LID) AT NORTH BOUND TELEGRAPH, A FOUR LANE ASPHALT SURFACED CONCRETE PAVEMENT, AND GODDARD ROADS, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 WITNESSES: N 48°12' E 80.56' CENTERLINE SOUTHWEST BOLT IN BASE OF STEEL LIGHT POLE (SUPRA)  
 S 30°28' E 88.86' CENTERLINE NORTHWEST BOLT IN BASE OF LAMP POST (SUPRA)  
 S 39°00' W 81.56' FOUND PK NAIL WITH TAG IN NORTHWEST SIDE OF UTILITY POLE (SUPRA) (W.C.B.L. 1A)  
 N 50°07' W 72.02' FOUND PK NAIL WITH TAG IN NORTHEAST SIDE OF UTILITY POLE (SUPRA) (W.C.B.L. 1A)  
 S 40°31' E 67.43' SET NAIL/SHINER IN SOUTHWEST SIDE OF UTILITY POLE

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE 3/4" IRON ROD AT E-7

Signed by E. Patrick O'Rourke  
 E. PATRICK O'ROURKE  
 Surveyor's Michigan License No. 16937

Date 12-27-94

L127797PA664

SECTION A (CONTINUED)

WITNESSES:	NNE	103.01	NAIL WEST SIDE 18" ELM (GONE)
	NE	90.43	NAIL NORTHWEST SIDE 28" WILLOW (GONE)
	SE	103.76	NAIL NORTHEAST SIDE 12" MAPLE (GONE)
	SW	98.95	NAIL SOUTHEAST SIDE 9" CHERRY (GONE)
	SW	46.41	CROSS ON SIGN (GONE)
	NW	82.40	U.S.C.G.S. #1E (GONE)