

SURVEY & REMONUMENTATION

RC 1510

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA667

For corners in

WAYNE <small>(County)</small>	Located In:	Corner Code #
	CITY OF TAYLOR TWP. #14	
1. Public Land Survey	T 3S R 10E	E-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *DOJ.*

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1510

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on OCT. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817
 G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
 WITNESSES: WO 10 N 46 W 3.10 (204.60' R) (GONE)
 BO 9 S 9 E 2.33 (153.78' R) (GONE)
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
 W.P.A. (1930's) IRON (NW-33) #139

(CONTINUED ON BACK)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND EMPTY HANDHOLE ROAD BOX (USED CENTERLINE) AT NORTHBOUND TELEGRAPH AND EUREKA ROADS.
 DISTANCE TO D-11 TRAVERSED AS 2643.41'; RECORD W.P.A. (1930) DISTANCES OF 2643.84' AND 2644.06'
 DISTANCE TO E-10 TRAVERSED AS 2628.95'; RECORD W.P.A. (1930) DISTANCES OF 2628.75' AND 2628.61'
 DISTANCE TO F-11 TRAVERSED AS 2679.40'; RECORD W.P.A. (1930) DISTANCES OF 2678.10' AND 2678.44'
 DISTANCE TO E-12 TRAVERSED AS 2573.33'; RECORD W.P.A. (1930) DISTANCES OF 2573.24' AND 2573.02'
 NO OTHER L.C.R.C. ARE ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS

\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:04 A.M. RECEIPT# 48A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 SECTION CORNER, 28, 29, 32 & 33, T.3S, R.10E
 SET CONCRETE MONUMENT WITH IRON ROD IN A HANDHOLE ROAD BOX AT NORTHBOUND TELEGRAPH, A FIVE LANE ASPHALT SURFACED CONCRETE PAVEMENT, AND EUREKA ROAD, A FIVE LANE CONCRETE PAVEMENT, AND IT HAS BEEN ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N 53°26' W 85.54' FOUND PK/DISC ON SOUTHWEST SIDE OF UTILITY POLE
 S 56°14' W 69.83' FOUND PK/DISC ON SOUTHEAST SIDE OF UTILITY POLE
 S 51°20' E 63.68' FOUND PK/DISC ON SOUTHWEST SIDE OF UTILITY POLE
 N 45°08' E 69.07' TIP OF ARROW ATOP BELL OF A FIRE HYDRANT

PLACED A REMONUMENTATION BRASS DISK AND PVC CAP #16937 ON ABOVE 3/8" IRON ROD.

Signed by *E. Patrick O'Rourke* Date 12-27-94
 Surveyor's Michigan License No. 16937

0101 11

LI27797PA668

SECTION A (CONTINUED)

WITNESSES: NE 59.91' NAIL SOUTHEAST SIDE TELEPHONE POLE (GONE)
SE 34.15' INLET (GONE)
SW 77.10' NAIL NORTHWEST SIDE TELEPHONE POLE (GONE)
SW 148.07' U.S.C.G.S. G.1 (GONE)
NW 64.90' SOUTHEAST CORNER OF GAS STATION (GONE)