

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1509**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA665

For corners in

WAYNE (County)	Located In: CITY OF TAYLOR TWP. #14	Corner Code # E-13
1. Public Land Survey	T 3S R 10E	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-7-94  
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1509

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817  
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.  
WITNESSES: B.O. 12 N 69 E 60 (39.60' R) (GONE)  
D.O. 12 N 28 W 90 (59.40' R) (GONE)  
RESURVEY AT DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF SURVEYING  
W.P.A. (1930's) CROSS (SW 331) #165

\$ 16.00 MISCELLANEOUS RECORDING  
27 DEC 94 11:04 A.M. RECEIPT# 48A  
RECORDED  
EDBERT E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

(CONTINUED ON BACK)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND A 1-1/4" IRON IN A ROAD BOX AT INTERSECTION OF TELEGRAPH AND PENNSYLVANIA ROADS.  
DISTANCE TO D-13 MEASURED AS 2644.54'; RECORD W.P.A. (1930) DISTANCES OF 2644.49' AND 2644.84'  
DISTANCE TO E-12 MEASURED AS 2568.56'; RECORD W.P.A. (1930) DISTANCES OF 2568.27' AND 2568.29'  
DISTANCE TO F-13 MEASURED AS 2656.50'+/-; RECORD W.P.A. (1930) DISTANCES OF 2656.14' AND 2656.40'  
L.19606 P.716 NO DESCRIPTION OF CORNER ON RECORD (1976)  
N 41° E 74.01' COMMON NAIL IN DETROIT EDISON POLE (GONE)  
S 52° E 68.51' PK NAIL IN DETROIT EDISON POLE (GONE)  
N 49° W 72.21' PK NAIL IN DETROIT EDISON POLE (MEAS. 72.38')  
L.20371 P.460 FOUND IRON IN MONUMENT BOX (1978)  
N 47° E 87.20' NAIL AND CAP IN WOOD POLE (GONE)  
S 45° E 86.30' CORNER OF FENCE POST (GONE)  
N 43° W NO DISTANCE NAIL AND CAP IN WOOD POLE (MEAS. 72.38')

(CONTINUED ON BACK)



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-13 SECTION CORNER 32, 33 T.3S., R.10E  
~~FOUND~~ A 1-1/4" IRON IN A ROAD BOX AT INTERSECTION ON TELEGRAPH AND PENNSYLVANIA ROADS, A FIVE LANE ASPHALT SURFACED CONCRETE INTERSECTION, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
N 40°27' E 74.86' SET NAIL WITH SHINER ON NORTHWEST SIDE OF UTILITY POLE  
S 53°00' E 72.10' FOUND PK NAIL ON NORTHEAST SIDE OF A UTILITY POLE (SUPRA)  
S 49°27' W 63.65' FOUND "X" CUT IN NORTH RIM OF A GAS COMPANY MANHOLE (SUPRA)  
N 50°43' W 72.38' FOUND PK NAIL WITH BRASS TAG ON NORTHEAST SIDE OF UTILITY POLE (SUPRA)

PLACED A MANGLED REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON AND IN ABOVE 1-1/4" IRON PIPE E-13.

Signed by E. Patrick O'Rourke  
Surveyor's Michigan License No. 6937

Date 12-27-94

L127797PA666

SECTION A (CONTINUED)

WITNESSES: NE 79.06 SW CORNER OF SCHOOL (GONE)  
SE 9.45 IRON (GONE)  
SW 51.93 20" OAK (GONE)  
NW 31.89 CROSS ON BASE OF ROAD SIGN POST (GONE)

SECTION B (CONTINUED)

L.23670 P.525 FOUND 3/4" IRON PIPE IN MONUMENT BOX (1988)  
N 40° E 74.77' PK NAIL WEST SIDE OF DETROIT EDISON POLE (GONE)  
S 53° E 72.09' PK NAIL NORTHWEST SIDE OF DEADMAN POLE (MEAS. 72.10')  
S 47° W 63.62' "+" CUT NORTH RIM GAS MANHOLE (MEAS. 63.65')  
N 51° W 72.36' NAIL EAST SIDE OF DETROIT EDISION POLE (MEAS. 72.38')