

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 10.00 DEED

12 DEC 96 2:13 P.M. RECEIPT# 629

RECORDED
FOREST E. YOUNGWOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

LIBER 29337 PAGE 550

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-13-96
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9							
5												
6	18		17		16		15		14		13	
7												
8	19		20		21							
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



96219296

For corners in

WAYNE (County) Located in: CITY OF TAYLOR TOWNSHIP #14 Corner Code # F-11

1. Public Land Survey T3S R10E F-11
T R
T R SURVEY &
T REMONUMENTATION

2. Property Controlling in Section S T R
S T R JEC 01 2000

3. Miscellaneous Property in Sec. S T R
S T R SECTION

4. Lot No. , Recorded Plat

5. Private Claims

I, WALTER J. ZBIKOWSKI, in a field survey on SEPTEMBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, remonumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. (1815-1817)
G.L.O. (1817), WEST ON TRUE LINE BETWEEN SEC 28-33, 40.04 (CHAINS) SET 1/4 SEC COR AT AVERAGE DIST.
(DESCRIPTION OF CORNER NOT STATED IN NOTES)

WITNESSES: POPE 9" N 20 W 1.10 (LINKS) (0.73') (GONE)
DO 9" N 11 W 1.07 (LINKS) (0.71') (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

W.P.A. (1930's) CROSS SET, N-83 (#138)

WITNESSES: ESE 9.10' CROSS (IN ROAD) (GONE)
SE 44.40' 8" ELM (GONE)
SW 53.73' 6" ELM (GONE)
NNW 34.30' EDISON POLE (GONE)
N&S 8.35' AND 11.90' EDGES OF ROAD RESPECTIVELY (NOW NEW FIVE LANE PAVEMENT)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

FOUND A CONCRETE MONUMENT IN A ROAD BOX (GOOD) IN THE CENTER LANE OF EUREKA ROAD (A FIVE LANE ASPHALT SURFACED CONCRETE PAVEMENT) JUST EAST OF PARDEE ROAD TO THE NORTH (A FIVE LANE CONCRETE PAVEMENT) DISTANCE TO G-11 MEASURED AS 2629.85'; G.L.O. (1817) RECORD DISTANCE OF 40.04 CHAINS (2642.64'); W.P.A. (1930's) RECORD DISTANCES OF 2629.10' AND 2629.13'; "SUPERVISOR'S TAYLOR PLAT NO. 10" L.66 P.27 (1938) RECORD DISTANCE OF 2629.19'; DISTANCE TO F-12 TRAVERSED AS 2599.55'; "SUPERVISOR'S TAYLOR PLAT NO. 10" L.66 P.27 (1938) RECORD DISTANCE OF 2600.61';

DISTANCE TO E-11 TRAVERSED AS 2679.49'; G.L.O. (1817) RECORD DISTANCE OF 40.04 CHAINS (2642.64'); W.P.A. (1930's) RECORD DISTANCES OF 2678.10' AND 2678.44'

L.18744 P.781 FOUND 1/2" IRON BAR IN MONUMENT BOX (1974) LCRC #312

WITNESSES: S.35°E. 63.08' PK NAIL IN NORTHEAST FACE OF UTILITY POLE (GONE)
S.35°W. 54.34' PK NAIL IN EAST FACE OF UTILITY POLE (GONE)
N.25°W. 78.93' CHISELED "X" ON NORTHEAST BOLT OF LIGHT POLE (NOW GONE) (MEASURED 79.51', 10/2/95)

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

F-11, SECTION CORNER 28. 33 T.3S., R.10E.

PLACED A BRASS REMONUMENTATION DISC AND PVC CAP #21586 ON REBAR IN CONCRETE MONUMENT IN A ROAD BOX IN THE CENTER LANE OF EUREKA ROAD (A FIVE LANE ASPHALT SURFACED CONCRETE PAVEMENT) JUST EAST OF PARDEE ROAD TO THE NORTH (A FIVE LANE CONCRETE PAVEMENT), AND IT IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N.59°21'E. 110.45' FOUND CHISELED "X" IN NW BOLT TO BASE OF STEEL LIGHT POLE
S.16°24'W. 53.56' FOUND CHISELED "X" IN NW BOLT TO BASE OF STEEL LIGHT POLE (SUPRA)
S.58°54'W. 108.10' FOUND 60d SPIKE IN ALUM. DISC ON SE SIDE OF UTILITY GUY POLE (SUPRA)
N.37°24'W. 144.12' FOUND 60d SPIKE IN ALUM. DISC ON NE SIDE OF UTILITY POLE (SUPRA)

ABOVE CONCRETE MONUMENT F-11.

Signed by Walter J. Zbikowski
WALTER J. ZBIKOWSKI
Surveyor's Michigan License No. 21586

Date DEC. 11, 1996

B. CONTINUED

L.18906 P.293 MONUMENT BOX (1974) C.S. #968

WITNESSES: N.10°00'E. 89.73' SOUTHWEST BOLT IN LIGHT TOWER (GONE)
S.45°00'E. 63.04' PK NAIL IN MICHIGAN BELL TELEPHONE POLE (GONE)
S.45°00'W. 54.33' PK NAIL IN DETROIT EDISON SUPPORT POLE (GONE)

L.24002 P.143 FOUND MONUMENT IN MONUMENT BOX (1988) LCRC #931

WITNESSES: S.20°W. 53.53' CHISELED "X" IN NORTHWEST BOLT LIGHT POLE (MEASURED 53.56')
S.60°W. 107.93' SET 60d SPIKE AND DISC SOUTHEAST FACE GUY POLE (MEASURED 108.10')
N.45°W. 143.88' SET 60d SPIKE AND DISC, NORTHEAST FACE UTILITY POLE (MEASURED 144.12')
N.20°W. (NO DIST) FOUND CHISELED "X", NE BOLT LIGHT POLE (NOW GONE - MEASURED 79.51', 10/29/95)

**SURVEY &
REMONUMENTATION**

JEC 01 2000

SECTION

FILE DO NOT MAIL