

FEB 28 1994

RC 1295

LI 27033 PA 881

COMMERCIAL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: WAYNE (County), Located In: CITY OF TAYLOR, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-93 [Signature]
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1295

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 2.

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.

WITNESSES: B. ASH 12 SOUTH 8 (5.28') (GONE)
ELM 9 N36E 4 (2.64') (GONE)

W.P.A. (1930's) - FOUND IRON (#20)

WITNESSES: NE'LY 62.72' NAIL E. SIDE 15" MAPLE (GONE)
NE'LY 33.93' NAIL SE SIDE 18" ELM (GONE)
SW'LY 40.85' NAIL NW SIDE 15" ELM (GONE)
W'LY 38.95' NAIL N. SIDE 18" SYCAMORE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO G3 MEASURED AS 2634.75'; RECORD W.P.A. (1930) DISTANCES OF 2633.71' AND 2634.02';

L.17791 P.775 (C.S.) - FOUND W.C.R.C. MONUMENT BOX (1971)
NO WITNESSES SHOWN ON ABOVE (C.S.)

L.18022 P.40 (C.S.) - FOUND 1/2" IRON IN MON. BOX (1972)
S. 86°E 51.20' P.K. NAIL IN MBT POLE (GONE)
S. 55°E 62.43' P.K. NAIL IN DE POLE (MEAS. 62.42')
S. 65°W 77.95' P.K. NAIL IN DE POLE (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 SECTION CORNER 3 & 4, T3S, R10E.

FOUND CONCRETE MONUMENT IN A HANDHOLE ROAD BOX IN MONROE ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: S. 55°07'E 63.04' FOUND NAIL IN TAG #21566 ON SW SIDE OF UTILITY POLE (SUPRA)
S. 67°36'W 83.11' FOUND NAIL IN TAG #21566 ON N SIDE OF UTILITY POLE (SUPRA)
N. 15°55'W 103.53' FOUND NAIL IN TAG #21566 ON E SIDE OF DE LIGHT POLE (SUPRA)
N. 29°04'E 113.06' FOUND NAIL IN TAG #21566 ON NW SIDE OF UTILITY POLE (SUPRA)

PLACE A REMONUMENTATION BRASS AND CAP #16937 ION ABOVE FOUND CONCRETE MONUMENT G2.

Signed by [Signature] Date NOVEMBER 30, 1993
Surveyor's Michigan License No. 16937



2K

12/13/93 35696 REMO FEE 2.00
12/13/93 35696 DEED 14.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.18022 P.27 - FOUND 1/2" IRON BAR IN MONUMENT BOX (1972)
SAME WITNESSES AS L.18022 P.40 ABOVE (C.S.)

L.18396 P.304 (C.S.) - FOUND 1/2" IRON IN CONC. (1973)
S. 89°16'E 51.20' P.K. NAIL IN MBT POLE (GONE)
S. 58°43'E 62.50' P.K. NAIL IN ED POLE (MEAS. 62.42')
S. 62°10'W 78.00' P.K. NAIL IN ED POLE (GONE)

UNRECORDED (C.S.) - FOUND CONCRETE MONUMENT IN MONUMENT BOX (1989)
N. 29°07'E 113.07' POWER POLE (MEAS. 113.06')
S. 55°04'E 63.03' UTILITY POLE (MEAS. 63.04')
S. 67°35'W 83.06' UTILITY POLE (MEAS. 83.11')
N. 15°51'W 103.54' POWER POLE (MEAS. 103.52')

DISTANCE TO G3 SHOWN AS 2634.61'; (NEAS. 2634.75')