

FILE DO NOT MAIL

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 02 1999

Liber-30034

For corners in

City of

SECTION

Wayne
(County)

Located In: Taylor Twp. Corner Code #

- 1. Public Land Survey T-3-S R-10-E G-5
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, John N. Redash, in a field survey on Dec. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theroforo as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1817), North 80.00 chains, Corner sections 3, 4, 9, and 10 (description of corner not stated in notes)
Witnessed as: W. Ash 10" N. 77° W. 12 (links) (gone)
Elm 9" S. 11° W. 15 (links) (gone)

W.P.A. (1930's), Iron (#59)
Witnessed as: N.E. 84.95 Mon. (84.91 meas.)
N.E. 50.05 12" Elm (gone)
S. 30.15 14" Elm (gone)
N.W. 42.74 Ed. pole (relocated)
S.W. 51.13 10" Elm (gone)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monument was found currently occupying this corner. No further witnesses are of record. I re-established this corner with existing monumentation from "Sloan's Monroe Boulevard Park Subdivision" as recorded in Liber 61, Page 61, Wayne County Records. Field measurements were observed between the following corners:

G-4 to G-5			G-5 to H-5		
2636.15	Meas.		2622.03	Meas.	
2640.00	Rec.	G.L.O.	2629.11	Rec.	G.L.O.
2636.42	Rec.	WPA	2621.58	Rec.	WPA
2636.69	Rec.	WPA			

\$4.00 REMONUMENTATION
\$7.00 DEED
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #101786

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5, Section corner 9, 10, 11, and 12, T-3-S., R-10-E.
I placed a 3/4" iron rod with remonumentation brass disk #37281 in a new monument box at the intersection of Wick and Monroe Roads, and it is accepted as a careful and faithful perpetuation of the position of the original corner.

Witnesses: N. 51° E., 84.91' Found concrete monument
N. 77° E., 104.65' Set mag nail and Wayne County Remon. tag S. face U-pole
S. 29° W., 63.50' Set mag nail and Wayne County Remon. tag S.W. face U-pole
N. 37° W., 43.68' Set mag. nail with Wayne County Remon. tag S.W. face of U-pole
S. 44° W., 83.52' Found 40d nail S.E. face U-pole

Signed by John N. Redash Date December 7, 1998
Surveyor's Michigan License No. 37281

R LCR 7 HR 1PG U