

FEB 28 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)	Located In: CITY OF TAYLOR	Corner Code #
1. Public Land Survey	T 3S R 10E	G-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 11-30-93 D.P.J.  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1308

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.  
 WITNESSES: BO 10 S56 E17 (11.22') (GONE)  
 DO 9 N17 W18 (11.88') (GONE)  
 W.P.A. (1930) - FOUND IRON (#85)  
 WITNESSES: NORTH 29.26' NAIL W. SIDE 24" MAPLE (GONE)  
 SE'LY 104.01' NW CORNER TO PORCH (GONE)  
 SSW'LY 46.69' NAIL E. SIDE 30" OAK (GONE)  
 SW'LY 99.52' NAIL E. SIDE 20" OAK (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO H7 MEASURED AS 2624.76'; RECORD W.P.A. (1930) DISTANCES OF 2625.15' AND 2624.59';  
 DISTANCE TO F7 MEASURED AS 2686.11'; RECORD W.P.A. (1930) DISTANCES OF 2685.61' AND 2685.89';

L.18729 P.625 & 626 (C.S.) - FOUND IRON IN MON. BOX (1974)  
 DISTANCE TO F7 RECORDED AS 2686.15'; (MEAS. 2686.11')  
 NO WITNESSES SHOWN ON ABOVE C.S.

L.19172 P.889 - FOUND CONCRETE MONUMENT IN HANDHOLE (1975)  
 N 3°E 52.95' NAIL E. SIDE D.E. POLE (GONE)  
 S 55°W 54.90' NAIL W. SIDE D.E. POLE (GONE)  
 N 50°W 64.0' SE BOLT ON LIGHT BASE (MEAS. 64.16')  
 NO OTHER SUBSEQUENT L.C.R.C. OR C.S. ARE RECORDED AT WAYNE COUNTY REGISTER OF DEEDS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 SECTION CORNER 15, 16, 21, & 22, T3S, R10E.  
 FOUND A CONCRETE MONUMENT IN A HANDHOLE ROAD BOX IN GODDARD ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N 05°52' E 53.01' SET NAIL IN SHINER ON E. SIDE OF A UTILITY POLE  
 N 56°15' W 64.16' FOUND C/L SE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE (SUPRA)  
 S 58°52' E 72.96' (SET) C/L NE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE  
 S 01°24' E 64.27' SET NAIL IN SHINER ON E. SIDE OF UTILITY GUY POLE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND MONUMENT G-7.



Signed by E. Patrick O'Rourke  
 Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993

2R  
11K D