

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)

Located In: CITY OF TAYLOR

Corner Code #

- 1. Public Land Survey T 3S R 10E G-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1297

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.

- WITNESSES: B0 12 N 45 W 134 (88.44') (GONE)
DO 9 N 10 W 82 (54.12') (GONE)
W.P.A. (1930's) WITNESS: ED POLE NW 21.60' (GONE) (IRON) #137
10" ELM NE 69.20' (GONE)
28" MAPLE SE 86.45' (GONE)
HEADWALL SE 65.65' (GONE)
CROSS S 11.36' (GONE)

- L.C.R.C. #209 L.18381 P.463
L.C.R.C. #313 L.18744 P.783
CS 968 L.18906 P.293
L.C.R.C. 815 L.21757 P.25
L.C.R.C. 931 L.24002 P.143

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO G10 MEASURED AS 2721.01'; RECORDED 1930 W.P.A. DISTANCES OF 2721.03' AND 2720.86';
DISTANCE TO H11 TRAVERSED AS 2636.63'; RECORDED 1930 W.P.A. DISTANCES OF 2636.79' AND 2636.80';
DISTANCE TO G11 MEASURED AS 2586.63'; RECORDED 1930 W.P.A. DISTANCES OF 2586.55' AND 2586.52';
DISTANCE TO F11 MEASURED AS 2629.85'; RECORDED 1930 W.P.A. DISTANCES OF 2629.10' AND 2629.13';

- L.18381 P.463 - FOUND IRON IN MONUMENT BOX (1972)
N.W. 79.05' P.K. NAIL IN POWER POLE (GONE)
N.E. 74.30' P.K. NAIL IN POWER POLE (MEAS. N41°16'E, 73.81')
S.E. 71.83' P.K. NAIL IN POWER POLE (GONE)
S.W. 96.10' P.K. NAIL IN POWER POLE (MEAS. S 59°58'W, 96.06')

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 SECTION CORNER 27, 28, 33, & 34, T3S, R10E.

FOUND 1/2" IRON PIPE IN CONCRETE IN A HANDHOLE ROAD BOX @ EUREKA AND RACHO ROADS AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- WITNESS: N 43°16' E 73.81' FOUND 60d SPIKE IN DISC ON SE SIDE UTILITY POLE (SUPRA)
N 71°18' W 150.74' FOUND CHISELED "X" ON SE ANCHOR BOLT IN BASE STEEL LIGHT POLE (SUPRA)
S 38°49' W 77.90' FOUND 60d SPIKE & DISC ON SE SIDE GUY POLE (SUPRA)
S 34°28' E 82.59' FOUND 60d SPIKE & DISC ON SW SIDE UTILITY POLE (SUPRA)

PLACED A REMONUMENTATION BRASS DISC AROUND AND CAP #16937 INSIDE FOUND 1/2" IRON G-11.

Signed by [Signature]
Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993



12/13/93 35696 REMO FEE 2.00
 12/13/93 35696 DEED 14.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.18744 P.783 - FOUND 1/2" IRON BAR IN MONUMENT BOX (1974)

N 40° E 74.16' P.K. NAIL IN N.W. FACE OF UTILITY POLE (MEAS. N 41°16'E, 73.81')
 S 40° W 78.45' P.K. NAIL IN S.E. FACE OF UTILITY POLE (MEAS. S 38°49'W, 77.67')
 N 60° W 79.11' P.K. NAIL IN S.W. FACE OF UTILITY POLE (GONE)

L.18906 P.293 (C.S.) - MONUMENT BOX (1974)

N 45°00' E 74.07' P.K. NAIL IN UTILITY POLE (MEAS. N 41°16'E, 73.81')
 S 40°00' E 71.66' P.K. NAIL IN M.B.T. POLE (GONE)
 N 60°00' W 79.26' P.K. NAIL IN D.E. POLE (GONE)

L.21757 P.25 - 1" STEEL PIPE (1983)

N 23°09'05" E 87.55' TOP BOLT OF FIRE HYDRANT (MEAS. N 29°47'E, 87.49')
 S 34°55'30" E 82.31' NAIL IN WOOD UTILITY POLE (MEAS. S 28°23'E, 82.67')
 S 32°45'35" W 78.52' NAIL IN WOOD UTILITY POLE (MEAS. S 39°31'W, 77.64')
 N 53°11'45" W 85.08' NAIL IN WOOD UTILITY POLE (GONE)

L.24002 P.143 - FOUND 1/2" PIPE IN MONUMENT BOX (1988)

N 50° E 73.78' 60d SPIKE & DISC, S.E. FACE UTILITY POLE (MEAS. 73.81')
 N 65° W 150.64' CHISELED "X" S.E. BOLT LIGHT POLE (MEAS. 150.74')
 S 40° W 77.81' 60d SPIKE & DISC, S.E. FACE GUY POLE (MEAS. S 38°49'W, 77.90')
 S 30° E 82.53' 60d SPIKE & DISC, S.W. FACE UTILITY POLE (MEAS. 82.59')