

SURVEY & REMONUMENTATION

RC 1512

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA671

For corners **COMMISSION**

WAYNE _____ Located in: _____ Corner Code # _____
 (County) CITY OF TAYLOR TWP. #14

1. Public Land Survey T 3S R 10E G-13
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12-7-94 *DPJ*
 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

RC 1512

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817
 G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
 WITNESSES: WO 16 N 27 W 6.38 (421.08' R) (GONE)
 ELM 20 N 9 E 8.29 (547.14' R) (GONE)
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
 W.P.A. (1930's) IRON SET (S-W 34) #163

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON ROD IN ROAD BOX (NO LID) AT INTERSECTION OF RACHO ROAD AND PENNSYLVANIA ROADS.
 DISTANCE TO F-13 MEASURED AS 2650.24'; RECORD W.P.A. (1930) DISTANCES OF 2650.56' AND 2650.26'
 DISTANCE TO G-12 MEASURED AS 2577.86'; RECORD W.P.A. (1930) DISTANCES OF 2577.22' AND 2577.26'
 DISTANCE TO H-13 TRAVERSED AS 2675.15'; RECORD W.P.A. (1930) DISTANCE OF 2674.91'

L.19121 P.681 FOUND IRON IN MONUMENT BOX (1974)

N 40° E 71.20' WAYNE COUNTY ROAD COMMISSION NAIL AND CAP IN WEST SIDE OF DETROIT EDISON POLE (GONE)
 S 60° E 104.50' PK NAIL IN SOUTHWEST SIDE OF MICHIGAN BELL TELEPHONE POLE (MEAS. 104.21')
 S 35° W 56.45' WAYNE COUNTY ROAD COMMISSION NAIL AND CAP ON SOUTHEAST SIDE OF MICHIGAN BELL TELEPHONE POLE (GONE)
 N 40° W 70.10' WAYNE COUNTY ROAD COMMISSION NAIL AND CAP ON SOUTHWEST SIDE OF DETROIT EDISON POLE (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 SECTION CORNER 33,34 T.3S, R.10E
 3/8" IRON ROD IN ROAD BOX AT INTERSECTION OF RACHO AND PENNSYLVANIA ROADS, TWO LANE CONCRETE ROADS WITH ASPHALT WIDENING LANES AT INTERSECTION, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 N 45°43' E 67.60' FOUND PK NAIL WITH BRASS TAG IN SOUTHEAST SIDE OF UTILITY POLE
 S 28°10' E 111.24' FOUND PK NAIL WITH BRASS TAG IN NORTHEAST SIDE OF UTILITY POLE
 S 43°49' W 71.84' FOUND PK NAIL IN NORTHWEST SIDE OF UTILITY POLE
 N 45°19' W 70.57' SET NAIL WITH SHINER IN NORTHEAST SIDE OF UTILITY POLE

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE 3/8" IRON ROD G-13.



\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:05 A.M. RECEIPT# 48A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

Signed by *E. Patrick O'Rourke*
 Surveyor's Michigan License No. 16937

Date 12-27-94

*214
MIS*

LI27797PA672

SECTION A (CONTINUED)

WITNESSES: NE 54.76 18" MAPLE (GONE)
NE 61.05 26" MAPLE (GONE)
SE 37.57 ROAD SIGN POST (GONE)
SW 38.57 20" MAPLE (GONE)
NW 35.92 EDISON POLE (GONE)