

SUBJECT TO
REMONUMENTATION

RC 1309

LI 27033 PA 901

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)	Located In: CITY OF TAYLOR	Corner Code # H-3
1. Public Land Survey	T 3S R 10E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-93 *[Signature]*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1309

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.

WITNESSES: W ASH 10" N38E 6 (3.96') (GONE)
B ASH 9" S49W 7 (4.62') (GONE)

W.P.A. (1930's) WITNESSES: MANHOLE NW 66.25' (GONE)
(IRON) IRON NE 73.50' (GONE)
TEL POLE SE 92.46' (GONE)
TEL POLE SW 52.40' (GONE)

L.C.R.C. 463 L.19333 P.4
CS - NOT RECORDED

FOREST COUNTY REGISTER OF DEEDS
 93 DEC 13 PM 5:29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO I3 MEASURED AS 2568.82'; RECORD W.P.A. (1930) DISTANCE OF 2586.66' AND 2588.75';
DISTANCE TO G3 MEASURED AS 2550.49'; RECORD W.P.A. (1930) DISTANCE OF 2549.99' AND 2550.40'

L.19333 P.4 - FOUND IRON ENCASED IN CONCRETE IN MONUMENT BOX (1975)

N. 55°50'E 69.10' ARROW ON FIRE HYDRANT (MEAS. 68.73')
N. 46°15'W 55.50' P.K. NAIL N.E./SIDE LIGHT POLE (GONE)
N. 24°23'W 76.50' FENCE CORNER (MEAS. N. 33°63'W, 76.55')
UNRECORDED (C.S.) FOUND 3/8" PIPE (1989)
N. 51°33'W 55.77' UTILITY POLE (GONE)
N. 73°58'E 108.64' UTILITY POLE (GONE)
S. 60°16'E 75.26' POWER POLE (GONE)
S. 57°57'W 108.80' NW ANCHOR BOLT IN CONCRETE BASE (MEAS. 108.84')

ONLY SUBSEQUENT L.C.R.C. AT WAYNE COUNTY REGISTER OF DEEDS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 SECTION CORNER 3 & 10, T3S, R10E.
FOUND CONCRETE MONUMENT IN A HANDHOLE ROAD BOX AT ECORSE AND MERRICK ROADS AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 46°08'E 68.73' FOUND CENTER OF TOP BOLT OF HYDRANT (SUPRA)
S 49°15'E 71.12' SET NAIL IN SHINER ON NE SIDE 10" MT. ASH
S 57°44'W 108.24' FOUND "X" CUT IN NE ANCHOR BOLT IN BASE OF CONC/STEEL LIGHT POLE
S 07°04'W 39.48' FOUND CENTER OF NE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND MONUMENT H-3.



Signed by *E. Patrick O'Rourke*
Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993

2R
11/30