

RC 1298

FEB 25 1994

LI 27033 PA 887

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: WAYNE (County), Located In: CITY OF TAYLOR, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-93 [Signature]
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-12. A dot is marked at the intersection of column G and row 7.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.

WITNESSES: POPLAR 10" N75W 57 (37.62) (GONE)
DO 10" S40W 100 (66.00) (GONE)

L.C.R.C. #739 L.21050 P.565 (7-24-80)
CS 1701 L.21050 P.847 (7-24-80)
CS 1885 L.22576 P.799-803 (10-28-85)
CS 1905 L.22769 P.548-552 (4-28-86)

W.P.A. (1930's) WITNESSES: 30" ELM NW 61.30 (GONE)
(IRON) 36" ELM NE 37.96 (GONE)
5" ELM SE 91.62 (GONE)
TOP OF HYD SW 140.03 (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO I7 MEASURED AS 2627.78'; RECORD W.P.A. (1930) DISTANCES OF 2627.52' AND 2627.63';
DISTANCE TO G7 MEASURED AS 2624.76'; RECORD W.P.A. (1930) DISTANCES OF 2625.15' AND 2624.59';

L.21050 P.565 - FOUND 1/2" IRON IN MONUMENT BOX (1980)
N. 55°41'E 89.55' P.K. NAIL W. SIDE 24" TREE (GONE)
S. 45°52'E 85.64' N.E. CORNER FOUNDATION TO BLOCK BUILDING (MEAS. 85.63')
S. 8°20'E 44.09' P.K. NAIL N. SIDE MBT POLE (GONE)
N. 38°42'W 90.69' SW COR. BRICK OF BUILDING (MEAS. 90.71')

L.21050 P.847 - FOUND 1/2" IRON IN MONUMENT BOX (1980)
SAME WITNESSES AS L.21050 P.565 ABOVE.

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H7 SECTION CORNER 15 & 22, T3S, R10E.
FOUND CONCRETE MONUMENT IN HANDHOLE ROAD BOX ON GODDARD ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: S. 45°51'E 85.63' FOUND NE CORNER OF BLOCK FOUNDATION TO BUILDING #21085 (SUPRA)
N. 38°10'W 90.71' FOUND SW CORNER OF BRICK BUILDING #21090 (SUPRA)
N. 41°01'E 38.75' FOUND SW CORNER TO RIM OF CATCH BASIN (SUPRA)
S. 2°00'W 35.16' FOUND CENTER NE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE (SUPRA)

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND CONCRETE MONUMENT H7.

Signed by [Signature]
Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993



12/13/93 35696 DEED 14.00
 12/13/93 35696 REMO FEE 2.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

UNRECORDED C.S. - FOUND 1/2" IRON IN MONUMENT BOX (1985)

S. 46°22'E 85.60' NE COR. FOUNDATION OF STONE FACE OF BLDG. (MEAS. 85.63')
 S. 2° 31'W 35.23' "X" IN NW BOLT OF METAL LIGHT POLE (MEAS. 35.16')
 S. 39°16'W 91.67' NE COR BRICK DRIVE THRU WALL (MEAS. 91.75')
 N. 38°42'W 90.69' SW COR BRICK OF BLDG. (MEAS. 90.71')

L.22576 P.799-803 (C.S.) - FOUND CONC. MON. IN HANDHOLE (1985)

N. 45°E 38.7' SW CORNER C.B. (MEAS. N. 41°01'E, 38.75')
 S. 30°E 85.6' NE CORNER (BLDG) #21085 (MEAS. 85.63')
 S. 3°W 35.32' NE ANCHOR BOLT (IN) LIGHT POLE BASE (MEAS. 35.16')

L.22769 P.548-552 (C.S.) - FOUND CONC. MON. IN HANDHOLE (1986)

SAME WITNESSES AS L.22576 P.799-803 ABOVE.