

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1511

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE _____ (County)	Located In: CITY OF TAYLOR TWP. #14	Corner Code # H-13
1. Public Land Survey	T 3S R 10E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L127797PA669
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-7-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1511

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817
 G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
 WITNESSES: B. ASH 12 S.64 E.17 (11.22') (GONE)
 HICKORY 12 N.11 W.11 (7.26') (GONE)
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION, REGISTER OF DEEDS
 W.P.A. (1930's) IRON (S 34) #162

\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:05 A.M. RECEIPT# 48A
 RECORDED
 PABST TAXATION, REGISTER OF DEEDS
 WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT IN ROAD BOX (NO LID) IN CENTER JOINT OF PENNSYLVANIA ROAD.
 DISTANCE TO G-13 TRAVERSED AS 2675.15'; RECORD W.P.A. (1930) DISTANCE OF 2674.91'
 DISTANCE TO I-13 MEASURED AS 2610.31'; RECORD W.P.A. (1930) DISTANCE OF 2609.68'

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 SECTION CORNER SOUTH OF 34, T.3S, R.10E
~~FOUND~~ CONCRETE MONUMENT IN ROAD BOX (NO LID) IN CENTER JOINT OF PENNSYLVANIA ROAD, A TWO LANE CONCRETE PAVEMENT, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 N 31°52' E 60.42' TIP OF ARROW ATOP FIRE HYDRANT BOLT NUT
 N 60°31' E 133.55' FOUND PK NAIL IN NORTHWEST SIDE OF 27" MAPLE
 S 05°42' W 52.04' SET NAIL WITH SHINER ON EAST SIDE OF UTILITY POLE
 N 30°42' W 94.69' CUT "X" ON WEST SIDE OF WESTERLY CYCLONE GATE POST
 DUE WEST 8.58' FOUND CONCRETE MONUMENT IN ROAD BOX, SECTION CORNER NORTH OF 3 T.4S, R.10E

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE CONCRETE MONUMENT H-13

Signed by E. Patrick O'Rourke
 Surveyor's Michigan License No. 16937

Date 12-22-94

1181

LI27797PA670

SECTION A (CONTINUED)

WITNESSES: NE 26.48 20" MAPLE (GONE)
SE 31.20 TELEPHONE POLE (GONE)
W 8.67 IRON (MEAS. 8.58')
NW 66.60 12" MAPLE (GONE)
NW 37.72 18" MAPLE (GONE)