

# FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE

## SURVEY & REMONUMENTATION

MAR 02 1999

Libert-30034

Page-441.0

For corners in

City of

Wayne (County)

Located In: Taylor Twp. Corner Code #

SECTION

1. Public Land Survey	T-3-S	R-10-E	I-4
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-98 *JPJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, John N. Redash, in a field survey on Dec. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10	●	11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1817), North 40.00 chains, 1/4 section corner (no description stated in notes)  
Witnessed as: Elm 20" S. 57° W. 26 (links) (gone)

W.P.A. (1930's), Iron (#48)  
Witnessed as: N.E. 70.6 Hydrant (70.49' meas.)  
S.E. 74.18 Monument (74.20 meas.)  
S.E. 96.0 Oak (± 96' meas. centerline 40" Oak)  
N.W. 74.53 Iron (gone)



12/28/1998 09:11AM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod in concrete monument in a monument box currently occupies this corner. No further witnesses or record. Field measurements were observed between the following corners:

I-3 to I-4		I-4 to I-5	
2621.74	Meas.	2620.14	Meas.
2640.00	Rec. G.L.O.	2640.00	Rec. G.L.O.
2621.38	Rec. W.P.A.	2619.35	Rec. WPA
2620.40	Rec. Plat L54, L64		
2620.40	Rec. Plat L53, P57		

~~\$4.00~~ REMONUMENTATION  
~~\$7.00~~ DEED  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
Receipt #101786

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4, West 1/4 corner Section 11, East 1/4 corner Section 10, T-3-S., R-10-E.  
I placed a remonumentation brass cap #37281 on the existing monument in monument box at the intersection of Champaign and Pelham Roads and it is accepted as a careful and faithful perpetuation of the position of the original corner.

Witnesses: N. 45° E., 55.71' Set P.K. nail and Wayne County Remon. tag in N.W. face of U-pole  
S. 49° E., 60.55' Set P.K. nail and Wayne County Remon. tag in N.E. face of U-pole  
S. 56° W., 49.07' Set P.K. nail and Wayne County Remon. tag in S.E. face of U-pole  
N. 50° W., 60.94' Set P.K. nail and Wayne County Remon. tag in S.W. face of U-pole  
N. 45° E., 70.49' Centerline t/nut fire hydrant  
S. 55° E., 74.20' Found concrete monument

Signed by John N. Redash

Date December 7, 1998

Surveyor's Michigan License No. 37281

R LCR 7 4R U JPJ