

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1513**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

WAYNE \_\_\_\_\_ (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 CITY OF TAYLOR AND SOUTHGATE TWP. #14

1. Public Land Survey T 3S R 10E I-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LI27797PA673

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *D.P.J.*  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. 1815-1817  
 G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.  
 WITNESSES: ELM 12 N 75 E 10 (6.60') (GONE)  
 B. ASH 10 N 21 W 20 (13.20') (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION  
 W.P.A. (1930's) CROSS (SE 34) #161

(CONTINUED ON BACK)



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND CONCRETE MONUMENT IN HANDHOLE ROAD BOX IN CENTER OF EASTBOUND ALLEN ROAD AT PENNSYLVANIA ROAD.  
 DISTANCE TO H-13 MEASURED AS 2610.31'; RECORD W.P.A. (1930) DISTANCE OF 2609.68'  
 DISTANCE TO I-12 TRAVERSED AS 2600.38'; RECORD W.P.A. (1930) DISTANCE OF 2600.10'  
 DISTANCE TO J-13 TRAVERSED AS 2639.94'; RECORD W.P.A. (1930) DISTANCE OF 2639.76'  
 L.18997 P.803 CONCRETE MONUMENT IN BOX (1974)

NW 69.96' SPIKE WITH BRASS TAG IN NORTHEAST SIDE OF DETROIT EDISON POLE (MEAS. 69.76')  
 NE 74.05' SPIKE WITH BRASS TAG IN NORTHWEST SIDE OF DETROIT EDISON POLE (MEAS. 74.11')  
 E 103.05' CONCRETE MONUMENT IN BOX AT NORTHWEST CORNER SEC. 2, T.4S, R.10E (MEAS. 103.33')  
 SW 51.22' SPIKE WITH BRASS TAG IN NORTHWEST SIDE OF DETROIT EDISON POLE (MEAS. 51.15')

(CONTINUED ON BACK)

\$ 16.00 MISCELLANEOUS RECORDING  
 27 DEC 94 11:05 A.M. RECEIPT# 48A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-13 SECTION CORNER 34, 35, T.3S, R.10E

~~FOUND~~ CONCRETE MONUMENT IN HANDHOLE ROAD BOX (~~NO TAG BUT GOOD CONDITION~~) AND IN CENTER OF EAST BOUND ALLEN ROAD LANE AT PENNSYLVANIA AND ALLEN ROADS, A FIVE LANE CONCRETE PAVEMENT INTERSECTION, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N 43°50' E 74.11' SPIKE WITH BRASS TAG ON NORTHWEST SIDE OF DETROIT EDISON POLE (SUPRA)  
 S 63°11' E 94.13' FOUND NAIL/TAG ON SOUTHWEST SIDE OF UTILITY GUY POLE  
 S 18°29' W 51.15' SPIKE WITH BRASS TAG ON NORTHWEST SIDE OF DETROIT EDISON POLE (SUPRA)  
 N 44°09' W 69.76' SPIKE WITH BRASS TAG ON NORTHEAST SIDE OF DETROIT EDISON POLE (SUPRA)  
 N 88°42' E 103.33' CONCRETE MONUMENT IN ROAD BOX (NORTHWEST CORNER SEC. 2, T.4S, R.10E)

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #16937 ON ABOVE CONCRETE MONUMENT I-13

Signed by

*E. Patrick O'Rourke*

Date

12-27-94

E. PATRICK O'ROURKE  
 Surveyor's Michigan License No. 16937

L127797PA674

SECTION A (CONTINUED)

WITNESSES: NE 58.50 SIGNAL (GONE)  
E 103.02 CROSS (MEAS. 103.33' TO CONCRETE MONUMENT)  
SE 48.60 16" ELM (GONE)  
SE 60.65 SIGN POST (GONE)  
SW 53.90 TELEPHONE POLE (GONE)  
NW 41.98 12" ASH (GONE)

SECTION B (CONTINUED)

L.20546 P.674 MONUMENT BOX IN CONCRETE PAVEMENT (1979)

S 20° W 51.27' NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN UTILITY POLE (MEAS. 51.15')  
N 43° W 69.85' NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN UTILITY POLE (MEAS. 69.76')