

WAYNE COUNTY
REMONUMENTATION

FEB 28 1984

COMMISSION

RC 1310

LI 27033 PA 902

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)	Located In: CITY OF SOUTHGATE	Corner Code # K-11
1. Public Land Survey	T 3S R 10E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-30-93 [Signature]
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1310

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.

WITNESSES: HICKY 10" S47 W8 (5.28') (GONE)
DO 11" S57 E35 (23.10') (GONE)

W.P.A. (1930's) WITNESSES: MON N. 24.12
(IRON) #133 6" THORN NE 43.78
N. COR. RD. MON. BASE SE 42.64
TEL POLE SW 39.34

L.C.R.C. #384 L.19014 P.189
C.S. #1072 L.19014 P.201

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO L11 MEASURED AS 2613.16'; RECORD W.P.A. (1930) DISTANCES OF 2612.97' AND 2613.19';
DISTANCE TO J11 MEASURED AS 2644.98'; RECORD W.P.A. (1930) DISTANCE OF 2644.68';

L.19014 P.189 - FOUND IRON IN HANDHOLE (1974)
S50°E 61.89' P.K. NAIL IN S.W. SIDE MBT POLE (GONE)
S36°E 25.40' N.W. CORNER OF CATCH BASIN (GONE)
S55°W 72.44' R.R. SPIKE IN N. SIDE 36" ELM (GONE)
N28°W 59.46' P.K. NAIL IN N.E. SIDE A.T.&T. MARKER POST (GONE)

L.19014 P.201 (C.S.) - FOUND IRON IN HANDHOLE (1975)
WITNESSES ARE IDENTICAL TO ABOVE 1974 VERSION.
NO OTHER L.C.R.C. OR C.S. ARE RECORDED AT WAYNE COUNTY REGISTER OF DEEDS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 SECTION CORNER 25, 26, 35, & 36, T3S, R10E.
FOUND 1/2" IRON PIPE IN A HANDHOLE ROAD BOX @ EUREKA AND MCCANN ROADS AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 63°46' E 94.38' (SET) C/L SE ANCHOR BOLT IN BASE OF STEEL LIGHT POLE
S 41°35' N 55.44' (SET) C/L NW ANCHOR BOLT IN BASE OF STEEL LIGHT POLE
S 58°29' E 77.02' (SET) C/L TOP BOLT OF FIRE HYDRANT
S 20°20' E 67.31' (SET) C/L W. EDGE TO BASE OF STOP SIGN

PLACED A REMONUMENTATION BRASS DISC AROUND AND CAP #16937 INSIDE OF FOUND 1/2" IRON K-11.

Signed by [Signature]
E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

Date NOVEMBER 30, 1993

2R
11K7



FORREST & SORNGALOOD
REGISTERED PROFESSIONAL SURVEYORS
33 DEC 13 PM 5:29