

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **29337** PAGE **554**

For corners in

| | | |
|---------------------------------------|---------------------------------------|-------------------------------------|
| <u>WAYNE</u> (County) | Located in: | Corner Code # |
| | CITY OF SOUTHGATE TAYLOR TOWNSHIP #14 | |
| 1. Public Land Survey | T <u>3S</u> R <u>10E</u> L <u>9</u> | |
| | T_____ R_____ | |
| | T_____ R_____ | |
| | T_____ R_____ | |
| 2. Property Controlling in Section | S_____ T_____ R_____ | SURVEY & REMONUMENTATION |
| | S_____ T_____ R_____ | |
| 3. Miscellaneous Property in Sec. | S_____ T_____ R_____ | |
| | S_____ T_____ R_____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | SECTION |

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 11-13-96
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | | | | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, **WALTER J. ZBIKOWSKI**, in a field survey on OCTOBER 17, 1995, do hereby certify that under requirements of P.A. 75, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

ORIGINAL GOVERNMENT SURVEY BY JOSEPH FLETCHER, D.S. (1815-1817)
 G.L.O. (1816) SET 1/4 SEC COR AT AVERAGE DIST. (DESCRIPTION OF NOTES NOT STATED IN NOTES)

WITNESSES: BEECH 12 EAST 14 (9.24' REC) (GONE)
 DO 12 S 68 W 14 (9.24' REC) (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

W.P.A. (1930's) MON. N-25 (#106)
 WITNESSES: NE 69.06' BRICK PIER (GONE)
 SE 73.61' 18" MAPLE (GONE)
 SSE 41.35' 24" MAPLE (GONE)
 SW 69.15' BRICK PIER (GONE)
 WSW 73.74' FIRE HYDRANT (MEASURED 73.36')
 NW 69.80' BRICK PIER (GONE)

\$ 10.00 DEED
 12 DEC 96 2:14 P.M. RECEIPT# 628
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
 FOUND A 1/2" REBAR IN A ROAD BOX (GOOD) AT THE INTERSECTION OF NORTHLINE AND FORDLINE ROADS (BOTH CONCRETE PAVEMENT)

DISTANCE TO M-9 MEASURED AS 2599.56'; G.L.O. (1816) RECORD DISTANCE OF 39.90 CHAINS (2633.40'); W.P.A. (1930's) RECORD DISTANCES OF 2599.56' AND 2599.97'
 DISTANCE TO K-9 MEASURED AS 2621.29'; G.L.O. (1816) RECORD DISTANCE OF 39.90 CHAINS (2633.40'); W.P.A. (1930's) RECORD DISTANCES OF 2621.32' AND 2620.83'
 DISTANCE TO L-10 MEASURED AS 2623.01'; W.P.A. (1930's) RECORD DISTANCE OF 2623.78'
 "DIX-TOLEDO HIGHWAY SUBDIVISION" L.55 P.94 (1925) RECORD DISTANCE OF 2624.30'
 L.19055 P.863 FOUND CONCRETE MONUMENT IN HANDHOLE (1975) LCRC #410
 N.40°E. 59.61' PK NAIL NW SIDE TRAFFIC LIGHT SUPPORT POLE (GONE)
 S.30°E. 61.09' FACE OF 5" STEEL POLE (PEDESTRIAN SIGNAL) (MEASURED 61.06')
 S.48°W. 73.46' TOP NUT ON HYDRANT (MEASURED 73.36')

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L-9 SECTION CORNER 24, 25 T.3S., R.10E.
 9-23-96 PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #21586 ON THE 1/2" REBAR IN CONCRETE IN ROAD BOX AT THE INTERSECTION OF NORTHLINE AND FORDLINE ROADS (BOTH CONCRETE PAVEMENTS) AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N.51°43'E. 78.58' NAIL IN WCR BRASS WITNESS DISC ON SE SIDE TRIPLE 10" MAPLE
 S.34°16'W. 61.97' NAIL IN WCR BRASS REFERENCE DISC ON NW SIDE UTILITY POLE (SUPRA)
 S.45°49'W. 73.36' CENTER OF TOP BOLT OF FIRE HYDRANT (SUPRA)
 N.35°05'W. 44.60' SOUTH TIP OF RIM TO CATCH BASIN

Signed by Walter J. Zbikowski Date DEC. 11, 1996
 WALTER J. ZBIKOWSKI
 Surveyor's Michigan License No. 21586

96319298

- L.19940 P.441 FOUND HANDHOLE (1977) LCRC #548
 - N.45°E. 59.30' FACE OF WOODEN POLE (GONE)
 - N.45°W. 59.73' FACE OF STREET SIGN (GONE)
 - S.45°W. 61.80' FACE OF WOODEN POLE (MEASURED 61.70')
- L.22742 P.805 MONUMENT IN HANDHOLE (1986) LCRC #865
 - S.55°E. 81.32' PK NAIL IN NE SIDE OF 38" ELM (GONE)
 - S.40°W. 61.99' TAGGED NAIL (WCRC REF. DISC) IN NW SIDE OF UTILITY POLE (MEASURED 61.97')
 - S.45°W. 73.34' CENTERLINE OF TOP NUT OF FIRE HYDRANT (MEASURED 73.36')
 - N.35°E. 59.34' TAGGED NAIL I WEST SIDE OF GUY POLE (GONE)

SURVEY &
REMONUMENTATION

DEC 01 2000

SECTION

FILE DO NOT MAIL