

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: WAYNE (County), Located In: SUMPTER, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., and Lot No. / Recorded Plat.

Liber-30836 Page-37
99590841 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-99
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, STEVEN E. DUNN, in a field survey on February 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. SURVEYED BY ALEX HOLMES-1816

WPA RE-SURVEY OF ORIGINAL SECTIONS

WAYNE COUNTY BUREAU OF TAXATION

TIES TO SECTION CORNERS #91

1930'S SECTION

1930's

WAYNE COUNTY BUREAU OF TAXATION
WAYNE COUNTY BUREAU OF TAXATION

1/4 SECTION MAP-NW OF 19
1/4 SECTION MAP-SW OF 18

SEPTEMBER 5, 1952
JULY 27, 1970

BOARD OF WAYNE COUNTY ROAD COMMISSIONERS

SECTION CORNER WITNESS RECORD #91

MARCH 8, 1972

L.C.R.C.:

L.20551, P.446

Daniel Sandomierski #24616

Found P.K. Nail in road.

JUNE 22, 1979

WAYNE COUNTY BUREAU OF TAXATION

1/4 SECTION MAP-SW OF 18

1983

DEPARTMENT OF MANAGEMENT AND BUDGET
ASSESSMENT AND EQUALIZATION DIVISION:

1/4 SECTION MAP-NW of 19

1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-9 Section corner. Corner not common with M-7, T.4S., R.7E.

Found 3/4" Iron Pipe in Monument Box in asphalt road at centerline of Rawsonville Road and south of Tallady Road. Corner is 0.36' west of the Township Line.

I verified the location by comparing field measurements with record measurements of WPA Re-Survey of Original Sections.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

A-7 to A-8
WPA Re-Survey-2645.34'
Field-2645.23'

A-7 to B-7
GLO-46 chains (3036.00')
WPA Re-Survey-3083.09'
Field-3082.95'

A-7 to M-7 (T.4S., R.7E.)
GLO-1 chain, 36 links (89.76')
WPA RE-SURVEY-80±
Field-95.99'

Angle B-7/A-7/A-8
89°58'25" WPA Re-Survey
89°58'20" Field

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-7 Section corner. Not a common corner.

I REPLACED THE FOUND 3/4" IRON PIPE WITH A 1/2" BY 18" IRON ROD WITH ALUMINUM CAP STAMPED "WAYNE COUNTY REMONUMENTATION 28408" IN EXISTING MONUMENT BOX IN ASPHALT ROAD. NOT A COMMON CORNER.

WITNESSES:

- Az. 90° 24.25' Chiseled "+" on west rim of Gate Valve and Well.
Az. 150° 81.30' Set PK nail and Wayne County Remonumentation witness tag on southwest side of utility pole, above existing PK nail.
Az. 203° 83.41' Set PK nail and Wayne County Remonumentation witness tag on southeast side of utility pole.
Az. 205° 67.47' Found 60d nail on southeast side of 18" tree.
Az. 305° 58.34' Set PK nail and Wayne County Remonumentation witness tag on southeast side of utility pole.
Az. 0° 95.99' Found Iron Pipe in Monument Box in asphalt road. (M-7, T4S, R7E)

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn

Date Dec 21, 1999

Surveyor's Michigan License No. 28408

R LCR 9 4R 1Pg A



Grid table with columns A-M and rows 2-13. Contains numerical values and a date stamp 'FEB 23 2000'.