

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 28 2000

For corners in

WAYNE Located In: SUMPTER Corner Code # _____
 (County) SUMPTER

1. Public Land Survey T 4S R 8E A-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION 30836 Page-38
 Liber-30836 99590844 12/23/1999
 F.E. Youngblood, Wayne Co. Register of Deeds
 RDANDSYL

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-99 *DPZ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

I, **STEVEN E. DUNN**, in a field survey on February 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. SURVEYED BY ALEX HOLMES-1816

WPA RE-SURVEY OF ORIGINAL SECTIONS

1930's

WAYNE COUNTY BUREAU OF TAXATION

TIES TO SECTION CORNERS #117

1930's

WAYNE COUNTY BUREAU OF TAXATION
 WAYNE COUNTY BUREAU OF TAXATION

1/4 SECTION MAP-NW OF 30
 1/4 SECTION MAP-SW OF 19

REV. 1943
 REV. 1943

BOARD OF WAYNE COUNTY ROAD COMMISSIONERS

SECTION CORNER WITNESS RECORD #117

JANUARY 26, 1971

DEPARTMENT OF MANAGEMENT AND BUDGET
 ASSESSMENT AND EQUALIZATION DIVISION:

1/4 SECTION MAP-SW of 19
 1/4 SECTION MAP-NW of 30

1990
 1993

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-9 Section corner. Corner not common with M-9, T4S, R7E.

Found 3/4" Iron Pipe in Monument Box in asphalt road at centerline of Rawsonville Road and south of Willow Road. Corner is 0.83' east of the Township Line.

I verified the location by comparing field measurements with record measurements of WPA Re-Survey of Original Sections and witness tie of Board of Wayne County Road Commissioners Section Corner Witness Record.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

A-9 to A-10 (Remon Corner)
 WPA Re-Survey-2637.92'
 Field-2637.81'

A-9 to B-9
 GLO-46 chains (3036.00')
 WPA Re-Survey-3040.38'
 Field-3039.96'

A-9 to A-8
 WPA Re-Survey-2640.19'
 Field-2640.28'

A-9 to M-9 (T.4S., R.7E.)
 GLO-1 chain (66.00')
 Field-70.70'

Section Corner Witness Record:
 A-9 to M-9 (T.4S., R.7E.)
 70.84' (70.70' m)

Angle A-8/A-9/B-9
 90°50'10" WPA Re-Survey
 90°50'11" Field

Angle B-9/A-9/A-10
 89°19'00" WPA Re-Survey
 89°19'25" Field

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Section corner. Not a common corner.

I ACCEPTED THE IRON ROD WITH WASHTENAW COUNTY ROAD COMMISSION CAP STAMPED #37269 IN EXISTING MONUMENT BOX IN ASPHALT ROAD. NOT A COMMON CORNER.

WITNESSES:

Az. 60°	53.12'	Found PK nail and Wayne County Remonumentation witness tag on north side of light pole.
Az. 100°	23.69'	Set PK nail and Wayne County Remonumentation witness tag on south end of concrete curb return.
Az. 260°	23.77'	Set PK nail and Wayne County Remonumentation witness tag on south end of concrete curb return.
Az. 310°	38.16'	Set PK nail and Wayne County Remonumentation witness tag on south side of utility pole.
Az. 0°	70.70'	Found Iron Pipe in Monument Box in asphalt road. (M-9, T4S, R7E)

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn

Date Dec 21, 1999

Surveyor's Michigan License No. 28408

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983

R LCR 9 4R 18g A DPZ

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

