

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: WAYNE (County), Located In: SUMPTER, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Liber-30836 Page-39 99590846 12/23/1999 F.E. Youngblood, Wayne Co. Register of Deeds RDANDSYL

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-99 [Signature] WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on February 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO CORNER ORIGINALLY SET.

WPA RE-SURVEY OF ORIGINAL SECTIONS

1930's

WAYNE COUNTY BUREAU OF TAXATION

TIES TO SECTION CORNERS #118

1930's

WAYNE COUNTY BUREAU OF TAXATION WAYNE COUNTY BUREAU OF TAXATION

1/4 SECTION MAP-NW OF 30 1/4 SECTION MAP-SW OF 30

BOARD OF WAYNE COUNTY ROAD COMMISSIONERS

SECTION CORNER WITNESS RECORD #118 MARCH 3, 1972

DEPARTMENT OF MANAGEMENT AND BUDGET ASSESSMENT AND EQUALIZATION DIVISION:

1/4 SECTION MAP-SW of 30 1992 1/4 SECTION MAP-NW of 30 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: A-10 1/4 Section corner. Corner not common with M-10, T4S, R7E.

Found 3/4" Iron Pipe in Monument Box in asphalt road at centerline of Rawsonville Road. Corner is 0.17' east of Township Line.

I verified the location by comparing field measurements with record measurements of WPA Re-Survey of Original Sections and witness tie of Board of Wayne County Road Commissioners Section Corner Witness Record.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

Table with 3 columns: A-10 to A-11 (Remon Corner), A-10 to A-9 (Remon Corner), Angle A-9/A-10/A-11. Rows include WPA Re-Survey and Field measurements.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A-10 1/4 Section corner. Not a common corner.

I REPLACED THE 3/4" IRON PIPE WITH A 1/2" BY 18" IRON ROD WITH ALUMINUM CAP STAMPED "WAYNE COUNTY REMONUMENTATION #28408" IN EXISTING MONUMENT BOX IN ASPHALT ROAD. NOT A COMMON CORNER.

WITNESSES:

Table with 3 columns: Azimuth, Distance, Description. Includes bearings like Az. 60°, 155°, 275°, 310°, 0° and distances like 79.74', 75.74', 41.19', 38.16', 56.90'.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature] Surveyor's Michigan License No. 28408

Date Dec 21, 1999

R LCR 9 4R 1Pg A [Signature]