

FEB 28 2000

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE (County) Located In: SUMPTER Corner Code # A-11
1. Public Land Survey T 4S R 8E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Liber-30836 Page-40
99590847 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-99
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on February 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. SURVEYED BY ALEX HOLMES-1816

WPA RE-SURVEY OF ORIGINAL SECTIONS

WAYNE COUNTY BUREAU OF TAXATION

TIES TO SECTION CORNERS #143

WAYNE COUNTY BUREAU OF TAXATION
WAYNE COUNTY BUREAU OF TAXATION

1/4 SECTION MAP-NW OF 31
1/4 SECTION MAP-SW OF 30

BOARD OF WAYNE COUNTY ROAD COMMISSIONERS

SECTION CORNER WITNESS RECORD

DEPARTMENT OF MANAGEMENT AND BUDGET ASSESSMENT AND EQUALIZATION DIVISION:


1/4 SECTION MAP-SW of 30
1/4 SECTION MAP-NW of 31

1930's

REV. 1943
REV. 1943

MARCH 10, 1992

1992
1992



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-11 Section corner. Corner is not common with M-11, T.4S., R.7E., Washtenaw County

Found Iron Rod with Washtenaw County Road Commission cap stamped #37269 in Monument Box in asphalt road at centerline intersection of Rawsonville Road and Arkona Road.

I verified the location by comparing field measurements with record measurements of WPA Re-Survey of Original Sections and witness tie of Board of Wayne County Road Commissioners Section Corner Witness Record.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

Table with 4 columns: A-11 to A-12 (Remon Corner), A-11 to B-11, A-11 to A-10 (Remon Corner), A-11 to M-11 T.4S., R.7E.
Rows include GLO-40 Chains, WPA Re-Survey, Field measurements, and Section Corner Witness Record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-11 Section corner. Corner is not common with M-11, T.4S., R.7E., Washtenaw County.

I ACCEPTED THE IRON ROD WITH WASHTENAW COUNTY ROAD COMMISSION CAP STAMPED #37269 IN EXISTING MONUMENT BOX IN ASPHALT PAVEMENT. NOT A COMMON CORNER.

WITNESSES:

Table with 3 columns: Azimuth, Distance, Description.
Rows include: Az. 60° 79.74' Set PK nail and Wayne County Remonumentation witness tag on south side of utility pole.
Az. 155° 75.74' Set PK nail and Wayne County Remonumentation witness tag on southwest side of utility pole.
Az. 275° 41.19' Set PK nail and Wayne County Remonumentation witness tag on south side of 18" Oak.
Az. 310° 38.16' Found PK nail and Wayne County Remonumentation witness tag on east side of utility pole.
Az. 0° 56.51' Found Iron Rod with Washtenaw County Road Commission cap stamped #37269 in Monument Box in asphalt road. (M-11, T4S, R7E)

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn

Date Dec 21, 1999

Surveyor's Michigan License No. 28408

R LCR 9 4R 1Pg A-DJ