

FEB 29 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LI 27042PA342

For corners in COMMISSION

Wayne  
County:  
SUMPTER TOWNSHIP

Located in: Corner Code #

1. Public Land Survey	T 4 S	R 8 E	B-07
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 *[Signature]*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1320

I, Kenneth S. Wilkerson, in a field survey on October 09, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-07 Set Post - GLO - NO GLO WITNESSES REMAIN  
Iron - B of T  
Iron - WCRC - (3/14/72)  
Iron - L. 20551, P. 448 (4/03/79)

S 85 E 20.36 nail S face PP  
S 15 E 26.00 nail E face 15" hickory  
S 30 W 33.90 nail N face 24" tree  
N 45 W 99.13 SE edge san MH

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	•											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-07 Fd 1" iron

Verified by witnesses per L. 20551, P. 448

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County remonumentation washer and OHM - KSW 21584 cap on iron.

B-07 110 az 20.28 OHM tag S face PP  
165 az 26.30 OHM tag E face 15" hickory  
245 az 43.45 OHM tag N face 24" maple  
315 az 99.10 SE edge san. MH

The selected location is accepted as the best evidence of the position of the original corner.

Signed by: *[Signature]*

Date: Nov 15 1993

Drafted By: Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584



Orchard, Hiltz & McCliment, Inc.  
34935 Schoolcraft Road \* Livonia, Michigan 48150 \* Phone: (313) 522-6711

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

93 DEC 15 PM 4:59  
FOREST E. YOUNGSEL OOD  
REGISTER OF DEEDS  
WAYNE COUNTY, MI

2R  
11K1