

SURVEY & RECORDATION

FEB 28 1994

COMMISSION

RC 1323

LI 27042 PA 345

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne
County: SUMPTER TOWNSHIP

Located in: _____ Corner Code # _____

1. Public Land Survey T 4 S R 8 E C-07
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-15-93 [Signature]

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1323

I, Kenneth S. Wilkerson, in a field survey on October 09, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-07 Set Post - GLO - NO GLO WITNESSES REMAIN
Fd. Iron - S of T
Fd. 1/2" Rod - L. 24962, P. 737 (6/01/89)

- NE nail NW face 6" cherry
- NE 89.26 nail N face PP
- E 25.24 nail S face 4" cherry
- SW 78.74 nail E face 10' elm
- W 19.5 fence N & S
- Fence E & W
- NW 76.63 nail S face PP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-07 Fd 1/2" iron pipe

Meas. to North 2,644.96 R
2,646.33 M
2,654.49 R

Verified witness from corner certificate and measurements per L. 24962, P. 737

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County remonumentation washer and OHM - KSW 21584 cap on iron.

C-07 051 az 57.34 Set PK & washer in W face 22' oak
097 az 32.95 Fd iron PS 17623
160 az 71.90 Set PK & washer in W face 18" oak
306 az 33.80 Set PK & washer in S face 36" oak

The selected location is accepted as the best evidence of the position of the original corner.

Signed by: [Signature]

Date: _____

Drafted By: Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.
34935 Schoolcraft Road * Livonia, Michigan 48150 * Phone: (313) 522-6711

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

93 DEC 15 PM 4:59
FOREST E. YOUNG BLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI



FOR APPROVAL BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

2R
11K1